

TESTING LABORATORY SERVICES

1 General

1.1 RELATED WORK

.1 Coordinate the requirements of this section with all other sections, including but not limited to:

- .1 Section 02070 Demolition, Removal and Salvage
- .2 Section 02210 Rough Grading
- .3 Section 02212 Topsoil
- .4 Section 02233 Granular Base
- .5 Section 02511 Crusher Dust
- .6 Section 02515 Unit Paving
- .7 Section 02523 Concrete
- .8 Section 02552 Asphalt
- .9 Section 02872 Play Surfacing
- .10 Section 02875 Infields

1.2 QUALITY CONTROL

.1 **Consultant** to review requirements for inspection and testing with Contractor before start of Contract or Work pertaining to that section.

- .1 Notification is required before execution of any tests performed by testing laboratory.

1.3 APPOINTMENT

.1 Appoint testing laboratory for use in this Contract.

- .1 Named testing laboratory subject to approval.

2 Products (not applicable)

3 Execution

3.1 TESTING REQUIREMENTS

.1 **Consultant** to approve locations and extent of testing.

- .1 Submit test results for review.

TESTING LABORATORY SERVICES

- .2 Furnish all labour and facilities to ensure access to Work required for inspection and testing by testing laboratory.
 - .1 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
 - .2 Where materials are specified for testing, deliver representative samples in required quantity to testing laboratory.
- .3 Where tests or inspections reveal work not in accordance with Contract requirements, repair the work for additional testing (unless individual sections state otherwise).
 - .1 Repair and testing is to continue until the Work is done in accordance with Contract requirements.
- .4 Make good work disturbed by inspection and test.

END OF SECTION