

## NOTES:

- 1. CONCRETE STANDARD: 32 MPa DURA-MIX CONCRETE 5-8% AIR AS PER SPEC.
- 2. COMPACTION STANDARD: 98% STANDARD PROCTOR AS PER SPEC.
- 3. BROOM FINISH WALK, CURB FACE & GUTTER LONGITUDINALLY.
- 4. BROOM OVER ALL CONTROL JOINTS
- 5. SPACING OF CONTROL JOINTS TO BE 1.5M

	PLAN DESCRIPTION/REVISION	DATE	BY		APPROVALS
1	ORIGINAL STANDARD DRAWING	2020-JAN-31	PRZ	City of Saskatoon	Sapieha, Digitally signed Jurkiewi Digitally signed by Jurkiewicz, Matt
2	REVISED STANDARDS	2024-NOV-28	SJK	Saskatoon	Date: 2025.04.14 Date: 2025.05.01
					SIGNATURE 08:08:41 -06'00' SIGNATURE CZ, WIALL 13:29:20 -06'00' SIGNATURE
L					SIGNATURE SIGNATURE
L				TRANSITION TO 250mm VERTICAL CURB	NAME NAME
L					
L				APPROVED FOR USE AT TRANSIT STOPS	DATE SIGNED DATE SIGNED
L					SCALES: PLAN NO.
L					HOR. N.T.S. 102-0002-074r002
L					VERT. N.T.S. 102-0002-0741002