

CITY OF SASKATOON

Asbestos-Containing Building Materials Assessment Report - Lawson Heights Civic Centre and Rusty MacDonald Library



Submitted to:

The City of Saskatoon 1101 Avenue P North Saskatoon, SK S7L 7K6

Report Number: 1667963

Distribution:

One Copy: City of Saskatoon One Copy: Golder Associates Ltd.







Table of Contents

1.0	INTRO	DUCTION	. 1
2.0	SCOPE	E OF WORK	. 1
	2.1	Asbestos-Containing Materials	. 1
3.0	RESUL	TS AND DISCUSSION	. 2
	3.1	Asbestos-Containing Materials	. 2
	3.1.1	List of Identified Asbestos-Containing Materials	. 2
	3.1.2	Non Asbestos-Containing Materials	. 3
4.0	EXCLU	JDED AREAS AND MATERIALS	. 4
5.0	CONCI	LUSIONS AND RECOMMENDATIONS	. 4
	5.1	Asbestos-Containing Materials	. 4
6.0	SURVE	EY LIMITATIONS	. 5
7.0	CLOSI	JRE	. 6

APPENDICES

APPENDIX A

Laboratory Certificate of Analysis Report

APPENDIX B

Site Photographs

APPENDIX C

Room by Room Spreadsheet

APPENDIX D

Floor Plans





1.0 INTRODUCTION

Golder Associates Ltd. (Golder) was retained by the City of Saskatoon (the Client) to conduct an asbestos-containing building materials assessment of the Lawson Heights Civic Centre and Rusty MacDonald Library (the Site) located at 225 Primrose Drive in Saskatoon, Saskatchewan. This assessment report details our findings, conclusions and recommendations for the Site. A walkthrough of the Site was conducted on February 22, 2017 and the assessment was conducted on June 2 and 3, 2017 by Kody Henderson, OHS Project Manager. Asbestos-containing building materials were identified within the Lawson Heights Civic Centre and Rusty MacDonald Library during the assessment. Further information is provided in Section 3.0.

2.0 SCOPE OF WORK

In accordance with Tender 16-0844, Golder's scope of work included conducting an asbestos-containing building materials assessment of the Site to evaluate the quantities, locations, and conditions of asbestos-containing building materials.

Following the field work, Golder prepared this assessment report that includes laboratory analysis results, findings of the assessment, conclusions, and recommendations.

2.1 Asbestos-Containing Materials

The assessment involved a non-destructive inspection of the Site to assess the type and extent of suspect ACMs in the facility. The systems that were reviewed as part of the inspections included, but were not limited to:

- Structural systems including: insulation between solid webbed joists, fireproofing, building envelope, and interior/exterior caulking around windows and doors;
- Mechanical systems insulation including: hot water and steam system, condensate system, chilled water system, glycol system, domestic hot and cold water, emergency generator exhaust, boiler units, heat exchangers, and asbestos cement piping; and
- Architectural systems including: texture coats, sheet flooring, vinyl floor tile, acoustical spray-applied
 materials, condensation control applications, ceiling tile, wall board, drywall joint compound, and asbestos
 sheet products.

Systematic sampling of suspect ACMs was conducted as part of the assessment. Samples were submitted under chain of custody to International Asbestos Testing Laboratory Inc. (IATL) and analyzed for asbestos type and percentage content using Polarized Light Microscopy (PLM) in accordance with EPA methodologies (EPA 600/R-93/116).

Further information related to the assessment and sample collection methods can be found in the Golder document *Golder Asbestos Assessment General Survey Plan and Protocol* provided to the Client.





3.0 RESULTS AND DISCUSSION

The Lawson Heights Civic Centre and Rusty MacDonald Library were constructed in 1988 and consist of numerous change rooms, office spaces, as well as a swimming pool area, auditorium, and library. The Lawson Heights Civic Centre and Rusty MacDonald Library consist of three floors; a lower floor, main floor, and second floor. During the assessment, the pool area, auditorium, and all associated offices and change rooms on the main floor were treated as one functional space, the library area and associated offices were treated as a second functional space, the lower level as a third functional space, and the second floor as a fourth functional space.

- The Laboratory Certificate of Analysis report for the bulk asbestos samples is included in Appendix A.
- Photographs collected during the assessment are provided in Appendix B.
- A room by room spreadsheet outlining the locations, quantities, friability, and condition of identified asbestos-containing materials as well as additional information is provided in Appendix C.
- Floor plans outlining the sample locations and locations of identified asbestos-containing materials is provided in Appendix D.
- Please refer to Sections 4.0 and 6.0 of this report for a summary of the limitations encountered.

3.1 Asbestos-Containing Materials

A total of seventy-two (72) samples of building materials were collected and tested for asbestos content during the assessment of the Lawson Heights Civic Centre and Rusty MacDonald Library. One (1) of the samples was found to contain asbestos.

3.1.1 List of Identified Asbestos-Containing Materials

A list of the identified asbestos-containing materials is provided below.

Gold Sink Undercoat.

Further information on the identified asbestos-containing materials listed is provided below.

Gold Sink Undercoat

One (1) sample of gold sink undercoat was collected during the assessment. The sample collected was found to contain 2.7% Chrysotile asbestos. Asbestos-containing gold sink undercoat (see Photograph 1 in Appendix B) was observed in the following location:

- Room 105 (approximately 1 sink);
- Room 106 (approximately 1 sink); and
- Room 115 (approximately 1 sink).





3.1.2 Non Asbestos-Containing Materials

The following materials were sampled during this assessment and were found to not contain asbestos or were observed to be a non-suspect materials:

- Concrete scratch coat;
- Brown vinyl sheet flooring with white and dark brown flecks;
- Pipe-fitting insulation;
- Red/brown duct mastic;
- Drywall joint compound;
- Brown door caulking;
- Beige mosaic vinyl sheet flooring;
- Grey window frame caulking;
- Grey and blue speckled vinyl sheet flooring;
- 2'x4' Textured ceiling tile;
- Black window caulking;
- 2'x2' Ceiling tile with a square pattern;
- Grey window caulking;
- Red firestop;
- Stucco;
- Brick mortar;
- Red/brown building caulking;
- Grey building caulking;
- The drain lines throughout the site were not observed to have suspect packing;
- The duct work throughout the site was observed to be uninsulated or insulated with fibreglass insulation;
- The duct connector fabric throughout the site is not suspected to contain asbestos due to the vintage of construction;
- The 2'x4' ceiling tile with circular pattered fissures and the 2'x4' ceiling tile with small pinholes and small divots were date coded to a time period in which asbestos use was not widespread; and
- The boiler exhaust was observed to be insulated with fibreglass.





4.0 EXCLUDED AREAS AND MATERIALS

The following is a list of the areas and/or materials excluded during the assessment.

- During the assessment, approximately four floor locations were assessed for floor levelling compound. Floor levelling compound was not encountered at the time of the assessment. If floor levelling compound is encountered during renovation or demolition activities, additional sampling should be conducted to evaluate the presence or absence of asbestos.
- Building materials accessible by a ten foot ladder were assessed by Golder during the assessment. Materials located at heights that were inaccessible from a ten foot ladder were not assessed. If materials at heights are to be removed or impacted by future renovation or demolition activities, additional investigation and sampling of suspect materials may be required.
- The roof and associated components were not assessed by Golder during the assessment as per Tender 16-0844. If the roof and associated components are to be removed or impacted by future renovation or demolition activities, additional investigation and sampling of suspect materials may be required.
- Golder was unable to access Room 202A during the assessment as the room was locked and the Site Contact did not have keys. If work activities are scheduled within this area, further sampling may be required. If building materials within Room 104 are to be removed or impacted by future renovation or demolition activities, additional investigation and sampling of suspect materials may be required.

5.0 CONCLUSIONS AND RECOMMENDATIONS

Based on the visual assessment and the laboratory analytical results, the following project specific conclusions and recommendations are provided.

5.1 Asbestos-Containing Materials

Asbestos was positively identified within the gold sink undercoat on Site. Asbestos was not identified in the remaining samples collected and analyzed.

If the building is scheduled for renovations that will impact the identified asbestos-containing materials, it must be removed. If additional suspect asbestos-containing building materials are encountered during renovation activities, additional sampling should be undertaken to evaluate asbestos content.

Removal work should be completed by workers that are adequately trained in the hazards and proper methods of working with asbestos. Throughout the abatement activities, appropriate air monitoring and inspections should be conducted by a competent person to document that contamination is contained and that ACM are disposed of appropriately. Ensure asbestos waste is disposed of in accordance with the requirements of the Government of Saskatchewan.

All quantities listed in the report are approximate and are based on the conditions at the time of the assessment. Prior to abatement work it is recommended that a competent person conduct a review of the site to quantify and obtain all measurements of all building materials detailed in this report for cost estimating purposes.

In anticipation of potential abatement, Golder's recommendations for the asbestos-containing materials identified during the assessment are outlined below.





Gold Sink Undercoat

If scheduled for impact, asbestos-containing gold sink undercoat should be abated following low-risk abatement work procedures as outlined in the *Saskatchewan Asbestos Abatement Manual* (2017). Alternatively, as the gold sink undercoat was observed in good condition, and with a priority rating of 5 (please see the room by room spreadsheet provided in Appendix C for a description of the priority ratings), it can be managed in place if not scheduled for impact.

6.0 SURVEY LIMITATIONS

This report is based on data and information collected by Golder during the assessment conducted on June 2 and 3, 2017 and is based solely on site conditions encountered at the time of the assessment. Any use of this document or the findings, conclusions or recommendations provided in this report by any person other than the City of Saskatoon is at the sole risk of such user.

The conclusions and recommendations contained in this survey report are based upon professional opinions with regard to the subject matter. These opinions are in accordance with currently accepted environmental assessment standards and practices applicable to these locations and are subject to the following inherent limitations:

The data and findings presented in this report are valid as of the dates of the investigations. The passage of time, manifestation of latent conditions or occurrence of future events may warrant further exploration at the properties, analysis of the data, and re-evaluation of the findings, observations, and conclusions expressed in this report. No assurance is made regarding changes in conditions or practices subsequent to the time of the investigation. It was beyond the scope of this assessment to conduct a risk assessment and the potential health risks that may be associated with asbestos exposure for building occupants.

The data reported and the findings, observations and conclusions expressed in this report are limited by the Scope of Work. The Scope of Work was defined by Tender 16-0844 and the initial site walkthrough with the Client, the time and budgetary constraints imposed by the Client, and availability of access to the property.

Because of the limitations stated above, the findings, observations and conclusions expressed by Golder in this report are not, and must not be, considered an opinion concerning compliance of any past or present owner or operator of the site with any federal, provincial or local laws or regulations.

No warranty or guarantee, whether expressed or implied, is made with respect to the data or the reported findings, observations, and conclusions, which are based solely upon site conditions in existence at the time of investigation.

Golder's assessment reports present professional opinions and findings of a scientific and technical nature. While attempts were made to relate the data and findings to applicable environmental laws and regulations, the report shall not be construed to offer legal opinion or representations as to the requirements of, nor compliance with, environmental laws, rules, regulations or policies of federal, provincial, or local governmental agencies. Any use of the survey report constitutes acceptance of the limits of Golder's liability.

Golder's liability extends only to its client and not to other parties who may obtain this survey report. Issues raised by the report must be reviewed by appropriate legal counsel.





7.0 CLOSURE

We trust the information presented in this report meets your requirements. If you have any questions please contact Kody Henderson at (780) 483-3499 or email at kody_henderson@golder.com. Thank you for the opportunity to be of service. We look forward to working with you again in the future.





Report Signature Page

GOLDER ASSOCIATES LTD.

Prepared by: Reviewed by:

Kody Henderson, Dipl. Env. Sci., CRSP OHS Project Manager

Andrew Grant, B.Sc., P.Eng., EP, CRSP Associate, OHS Project Director

Order Crax

KH/AG/ba

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation.

\\golder\gal\edmonton\active\2016\3 proj\1667963 cityofsaskatoon_asbsurveys_saskatoon\07 reports\04 - lawson heights cc and rm\city of saskatoon - lawson heights cc and rm\ asbestos building material assessment report.docx





APPENDIX A

Laboratory Certificate of Analysis Report





9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

None Detected

Report Date: 6/15/2017

Report No.: 538138 - PLM

Asbestos Surveys - City of Saskatoon **Project:**

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258597 Analyst Observation: Grey Cementitious Location: Stairwell Adjacent Corridor B05

Client No.: A-001 Client Description: Concrete Scratch Coat **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected

Lab No.: 6258598 **Analyst Observation:** Grey Cementitious **Location:** Corridor B05

Client No.: A-002 Client Description: Concrete Scratch Coat **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

Trace Cellulose None Detected

Lab No.: 6258599 **Analyst Observation:** Lt Tan/White Vinyl Sheet Flooring **Location:** Corridor B05

Client No.: A-003 **Client Description:** Brown Vinyl Sheet Flooring With White **Facility:**

And Dark Brown Flecks

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: None Detected 100

None Detected

Lab No.: 6258600 **Analyst Observation:** Grey Insulation Location: Room B04

Client No.: A-004 Client Description: Pipe Fitting Insulation **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 35 Fibrous Glass 65

Trace Cellulose

Lab No.: 6258601 **Analyst Observation:** Grey Insulation Location: Room B04

Client No.: A-005 **Client Description:** Pipe Fitting Insulation **Facility:**

Percent Non-Fibrous Material: Percent Asbestos: Percent Non-Asbestos Fibrous Material:

35 Fibrous Glass None Detected

Lab No.: 6258602 **Analyst Observation:** Grey Insulation Location: Room B04

Client No.: A-006 **Client Description:** Pipe Fitting Insulation **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

35 Fibrous Glass 65 None Detected

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Signature:

06/15/2017 Date Analyzed:

Seely Harg

Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III Laboratory Director



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys – City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258603 Analyst Observation: Brown Mastic Location: Room B04

Client No.: A-007 Client Description: Red/Brown Duct Mastic Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258604 Analyst Observation: Grey Insulation Location: Corridor B03

Client No.: A-008 Client Description: Pipe-Fitting Insulation Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 40 Fibrous Glass

Trace Cellulose

Lab No.: 6258605 Analyst Observation: Grey Insulation Location: Room B01

Client No.: A-009 Client Description: Pipe-Fitting Insulation Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 40 Fibrous Glass

Lab No.: 6258606 Analyst Observation: Off-White Joint Compound Location: Corridor 154

Client No.: A-010 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258607 Analyst Observation: Brown Caulk Location: Room 155

Client No.: A-011 Client Description: Brown Door Caulking Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 100

Lab No.: 6258608 Analyst Observation: White Joint Compound Location: Room 165

Client No.: A-012 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Analytical Method - US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017

None Detected

Date Analyzed: 06/15/2017

Signature: Beiley Hargrove

Analyst: Rebecca Hargrove

Approved By:

Trail thanks

Frank E. Ehrenfeld, III Laboratory Director



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

6/15/2017

Client: Golder Associates Ltd Report Date:

16820 107 Ave Report No.: 538138 - PLM

Edmonton AB T5P 4C3 Project: Asbestos Surveys – City of Saskatoon

Client: GOL572 Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258609 Analyst Observation: Tan/Brown Vinyl Sheet Flooring Location: Room 165

Client No.: A-013 Client Description: Beige Mosaic Vinyl Sheet Flooring Facility:

<u>Percent Asbestos:</u> <u>Percent Non-Asbestos Fibrous Material:</u> <u>Percent Non-Fibrous Material:</u>

None Detected 10 Synthetic 9

Lab No.: 6258609(L2) Analyst Observation: Tan Mastic Location: Room 165

Client No.: A-013 Client Description: Beige Mosaic Vinyl Sheet Flooring Facility:

<u>Percent Asbestos:</u> <u>Percent Non-Asbestos Fibrous Material:</u> <u>Percent Non-Fibrous Material:</u>

None Detected None Detected 100

Lab No.: 6258610Analyst Observation: Grey CaulkLocation: Room 163

Client No.: A-014 Client Description: Grey Window Frame Caulking Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258611 Analyst Observation: Grey Cementitious Location: Room 159

Client No.: A-015 Client Description: Concrete Scratch Coat Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258612 Analyst Observation: Grey/White Cementitious Location: Room 160

Client No.: A-016 Client Description: Concrete Scratch Coat Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258613Analyst Observation: Grey CementitiousLocation: Room 150

Client No.: A-017 Client Description: Concrete Scratch Coat Facility:

<u>Percent Asbestos:</u> <u>Percent Non-Asbestos Fibrous Material:</u> <u>Percent Non-Fibrous Material:</u>

None Detected None Detected 100

Analytical Method - US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017

Date Analyzed: 06/15/2017

Signature: Becky Hargrove

Analyst: Rebecca Hargrove

Approved By:

Fronk Francisco

Frank E. Ehrenfeld, III Laboratory Director

Dated: 6/15/2017 5:25:37 PM Page 3 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys - City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258614 **Analyst Observation:** Grey Cementitious Location: Room 147

Client Description: Concrete Scratch Coat **Facility:** Client No.: A-018

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258615 Analyst Observation: Grey Cementitious Location: Room 141

Client No.: A-019 Client Description: Concrete Scratch Coat **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Analyst Observation: Off-White Joint Compound Lab No.: 6258616 **Location:** Room 138

Client Description: Drywall Joint Compound Client No.: A-020 **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258617 Analyst Observation: Grey/Blue Vinyl Sheet Flooring Location: Room 139

Client No.: A-021 Client Description: Grey And Blue Speckled Vinyl Sheet **Facility:**

Flooring

Percent Asbestos: Percent Non-Asbestos Fibrous Material:

None Detected 100 None Detected

Location: Room 139 **Lab No.:** 6258617(L2) **Analyst Observation:** Lt Tan Mastic

Client No.: A-021 Client Description: Grey And Blue Speckled Vinyl Sheet **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Asbestos:

Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258617(L3) **Analyst Observation:** Grev Leveling Compound Location: Room 139

Client Description: Grey And Blue Speckled Vinyl Sheet Client No.: A-021

Flooring

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

Trace Cellulose None Detected

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Date Analyzed: 06/15/2017

zeely Hargrove Signature:

Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III Laboratory Director

Facility:

Percent Non-Fibrous Material:



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys - City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258618 **Analyst Observation:** Tan/White Ceiling Tile Location: Room 139

Client Description: 2"x4" Textured Ceiling Tile **Facility:** Client No.: A-022

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

50 Cellulose None Detected

30 Fibrous Glass

Lab No.: 6258619 **Analyst Observation:** Tan/White Ceiling Tile **Location:** Room 140

Client Description: 2"x4" Textured Ceiling Tile Client No.: A-023 **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

50 Cellulose None Detected

30 Fibrous Glass

Lab No.: 6258620 **Analyst Observation:** Tan/White Ceiling Tile Location: Room 140

Client No.: A-024 Client Description: 2"x4" Textured Ceiling Tile **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

50 Cellulose None Detected

30 Fibrous Glass

Lab No.: 6258621 **Analyst Observation:** White Joint Compound **Location:** Corridor 161

Client No.: A-025 **Client Description:** Drywall Joint Compound **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Analyst Observation: White Joint Compound Lab No.: 6258622 **Location:** Room 131A

Client No.: A-026 Client Description: Drywall Joint Compound **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258623 **Analyst Observation:** Off-White Joint Compound **Location:** Room 132

Client No.: A-027 **Client Description:** Drywall Joint Compound **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Dated: 6/15/2017 5:25:38 PM

06/15/2017 Date Analyzed:

Zeeley Harg Signature:

Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III Laboratory Director



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys – City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258624 Analyst Observation: White Joint Compound Location: Room 130 A/B/C/D

Client No.: A-028 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258625 Analyst Observation: Grey/White Ceiling Tile Location: Room 130 A/B/C/D

Client No.: A-029 Client Description: 2'x4 Textured Ceiling Tile Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 50 Cellulose

35 Fibrous Glass

Lab No.: 6258626 Analyst Observation: Grey/White Ceiling Tile Location: Room 130 A/B/C/D

Client No.: A-030 Client Description: 2'x4 Textured Ceiling Tile Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 50 Cellulose

30 Fibrous Glass

Client No.: A-031 Client Description: Black Window Caulking Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 10 Cellulose 90

Lab No.: 6258628 Analyst Observation: Grey Insulation Location: Room 167/168

Client No.: A-032 Client Description: Pipe-Fitting Insulation Facility:

Tachty.

<u>Percent Asbestos:</u> <u>Percent Non-Asbestos Fibrous Material:</u> <u>Percent Non-Fibrous Material:</u>

None Detected 35 Fibrous Glass 65

Lab No.: 6258629 Analyst Observation: White Joint Compound Location: Room 103

Client No.: A-033 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017

Date Analyzed: 06/15/2017

Signature: Becky Hargrove

Analyst: Rebecca Hargrove

Approved By:

Frank E. Ehranfeld III

Frank E. Ehrenfeld, III Laboratory Director

Dated: 6/15/2017 5:25:38 PM Page 6 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys - City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258630 Analyst Observation: Off-White Joint Compound Location: Room 103

Client Description: Drywall Joint Compound **Facility:** Client No.: A-034

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258631 **Analyst Observation:** Grey/White Ceiling Tile Location: Room 103

Client No.: A-035 **Client Description:** 2'x2 Ceiling Tile With A Square Pattern **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 50 Cellulose

35 Fibrous Glass

Analyst Observation: Grey/White Ceiling Tile Location: Room 103 **Lab No.:** 6258632

Client Description: 2'x2 Ceiling Tile With A Square Pattern Client No.: A-036 **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: Percent Asbestos:

None Detected 50 Cellulose 15

35 Fibrous Glass

Location: Room 103 **Analyst Observation:** Grey/White Ceiling Tile Lab No.: 6258633

Client No.: A-037 **Client Description:** 2'x2 Ceiling Tile With A Square Pattern **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

50 Cellulose None Detected

35 Fibrous Glass

Analyst Observation: White Joint Compound **Lab No.:** 6258634 **Location:** Room 104

Client No.: A-038 Client Description: Drywall Joint Compound **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

None Detected None Detected

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Dated: 6/15/2017 5:25:38 PM

Date Analyzed: 06/15/2017

Zeeley Harg Signature:

Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III

Laboratory Director



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

80

Asbestos Surveys - City of Saskatoon **Project:**

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258635 **Analyst Observation:** Brown Vinyl Sheet Flooring Location: Children's Washroom

Client Description: Beige Mosaic Vinyl Sheet Flooring **Facility:** Client No.: A-039

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

15 Cellulose None Detected

5 Synthetic

Lab No.: 6258635(L2) **Analyst Observation:** Tan Mastic Location: Children's Washroom

Client No.: A-039 **Client Description:** Beige Mosaic Vinyl Sheet Flooring **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Asbestos: Percent Non-Fibrous Material:

None Detected None Detected

Analyst Observation: Grey/White Ceiling Tile Location: Children's Washroom Lab No.: 6258636

Client Description: 2'x4' Textured Ceiling Tile Client No.: A-040 **Facility:**

Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material: Percent Asbestos:

None Detected 45 Fibrous Glass

40 Cellulose

Analyst Observation: Grey/White Ceiling Tile Location: Room 105 Lab No.: 6258637

Client No.: A-041 Client Description: 2'x4' Textured Ceiling Tile **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

50 Cellulose None Detected

30 Fibrous Glass

Lab No.: 6258638 **Analyst Observation:** Black/Gold Insulation **Location:** Room 105

Client No.: A-042 Client Description: Gold Sink Undercoat **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 973 **PC 2.7** Chrysotile

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

06/15/2017 Date Analyzed:

Seely Harg Signature:

Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III Laboratory Director

Dated: 6/15/2017 5:25:38 PM Page 8 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys – City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258639 Analyst Observation: Grey/White Ceiling Tile Location: Room 109

Client No.: A-043 Client Description: 2'x4' Textured Ceiling Tile Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 45 Cellulose 15

40 Fibrous Glass

Lab No.: 6258640 Analyst Observation: Grey Putty Location: Room 103

Client No.: A-044 Client Description: Grey Window Caulking Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 10 Cellulose

Lab No.: 6258641 Analyst Observation: White Joint Compound Location: Room 108

Client No.: A-045 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258642 Analyst Observation: Sample Not Analyzed Location: Room 111

Client No.: A-046 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

Sample Not Analyzed Sample Not Analyzed

Not Analyzed, Insufficient Sample

Lab No.: 6258643 Analyst Observation: Off-White Joint Compound Location: Room 114

Client No.: A-047 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258643(L2) Analyst Observation: White Joint Compound Location: Room 114

Client No.: A-047 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017

Date Analyzed: 06/15/2017

Signature: Becky Hargrove

Analyst: Rebecca Hargrove

Approved By:

Frank F. Ehrenfeld III

Frank E. Ehrenfeld, III Laboratory Director



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys – City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258644 Analyst Observation: Off-White/White Joint Compound Location: Room 114

Client No.: A-048 Client Description: Drywall Joint Compound Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258645 Analyst Observation: Brown Mastic Location: Room 109

Client No.: A-049 Client Description: Red/Brown Duct Mastic Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 10

Lab No.: 6258646 Analyst Observation: Grey Insulation Location: Room 201

Client No.: A-050 Client Description: Pipe-Fitting Insulation Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 40 Fibrous Glass 66

Lab No.: 6258647 Analyst Observation: Grey Insulation Location: Room 201

Client No.: A-051 Client Description: Pipe-Fitting Insulation Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected 40 Fibrous Glass 66

Lab No.: 6258648 Analyst Observation: Red/Brown Caulk Location: Room 201

Client No.: A-052 Client Description: Red Firestop Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Lab No.: 6258649 Analyst Observation: White Insulation Location: Room 202B

Client No.: A-053 Client Description: Drywall Joint Compound Facility:

<u>Percent Asbestos:</u> <u>Percent Non-Asbestos Fibrous Material:</u> <u>Percent Non-Fibrous Material:</u>

None Detected None Detected 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017

Date Analyzed: 06/15/2017

Signature: Becky Hargrove

Analyst: Rebecca Hargrove

Approved By:

Frank F. Ehranfeld III

Frank E. Ehrenfeld, III Laboratory Director

Dated: 6/15/2017 5:25:38 PM Page 10 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys - City of Saskatoon

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258650 **Analyst Observation:** Sample Not Analyzed Location: Room 202B

Client Description: Drywall Joint Compound **Facility:** Client No.: A-054

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

Sample Not Analyzed Sample Not Analyzed

Not Analyzed, Insufficient Sample

Lab No.: 6258651 Analyst Observation: White Joint Compound **Location:** Room 202B

Client Description: Drywall Joint Compound Client No.: A-055 **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258652 **Analyst Observation:** Grey Insulation Location: Room 202B

Client Description: Pipe-Fitting Insulation Client No.: A-056 **Facility:**

Percent Non-Fibrous Material: Percent Asbestos: Percent Non-Asbestos Fibrous Material:

None Detected 35 Fibrous Glass

Trace Cellulose

Lab No.: 6258653 **Analyst Observation:** Tan/Grey Stucco **Location:** Exterior

Client Description: Stucco **Facility:** Client No.: A-057

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected Trace Fibrous Glass

Lab No.: 6258654 **Analyst Observation:** Grey Stucco **Location:** Exterior

Client No.: A-058 **Client Description:** Stucco **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258655 **Analyst Observation:** Grey Stucco Location: Exterior

Client No.: A-059 **Client Description:** Stucco **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Date Analyzed: 06/15/2017

Beely Hargrove Signature:

Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III Laboratory Director

Dated: 6/15/2017 5:25:38 PM Page 11 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

None Detected

Report Date: 6/15/2017

Report No.: 538138 - PLM

Asbestos Surveys - City of Saskatoon **Project:**

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258656 **Analyst Observation:** Grey Stucco **Location:** Exterior

Client Description: Stucco **Facility:** Client No.: A-060

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected

Lab No.: 6258657 **Analyst Observation:** Grey Stucco Location: Exterior

Client No.: A-061 Client Description: Stucco **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258658 **Analyst Observation:** Grey Stucco **Location:** Exterior

Client No.: A-062 Client Description: Stucco **Facility:**

Percent Non-Fibrous Material: Percent Asbestos: Percent Non-Asbestos Fibrous Material:

Trace Cellulose None Detected

Lab No.: 6258659 **Analyst Observation:** Grey Stucco Location: Exterior

Client No.: A-063 Client Description: Stucco **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258660 **Analyst Observation:** Red/Brown Mortar Location: Exterior

Client No.: A-064 Client Description: Brick Mortar Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258661 **Analyst Observation:** Red/Brown Mortar **Location:** Exterior

Client No.: A-065 Client Description: Brick Mortar **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Dated: 6/15/2017 5:25:38 PM

Date Analyzed: 06/15/2017

Beely Hargrove

Signature: Rebecca Hargrove **Analyst:**

Approved By:

Frank E. Ehrenfeld, III Laboratory Director



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Asbestos Surveys - City of Saskatoon **Project:**

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258662 **Analyst Observation:** Red/Brown Mortar **Location:** Exterior

Client Description: Brick Mortar **Facility:** Client No.: A-066

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258663 **Analyst Observation:** Red/Brown Mortar Location: Exterior

Client No.: A-067 Client Description: Brick Mortar **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258664 **Analyst Observation:** Red/Brown Mortar **Location:** Exterior

Client No.: A-068 Client Description: Brick Mortar **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Lab No.: 6258665 **Analyst Observation:** Red/Brown Mortar Location: Exterior

Client No.: A-069 Client Description: Brick Mortar **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

Trace Cellulose None Detected

Lab No.: 6258666 **Analyst Observation:** Red/Brown Mortar Location: Exterior

Client No.: A-070 Client Description: Brick Mortar Facility:

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

Trace Cellulose None Detected

Lab No.: 6258667 **Analyst Observation:** Tan Caulk Location: Exterior

Client No.: A-071 Client Description: Red/Brown Building Caulking **Facility:**

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

6/7/2017 **Date Received:**

Dated: 6/15/2017 5:25:38 PM

Signature:

Date Analyzed: 06/15/2017

Beely Hargrove

Rebecca Hargrove

Analyst:

Approved By:

Frank E. Ehrenfeld, III Laboratory Director

Page 13 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449 Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd

16820 107 Ave

Edmonton AB T5P 4C3

Client: GOL572

Report Date: 6/15/2017

Report No.: 538138 - PLM

Project: Asbestos Surveys – City of Saskatoon

Location: Exterior

Facility:

100

Project No.: 1667963

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258668 **Analyst Observation:** Tan Caulk

Client No.: A-072 Client Description: Grey Building Caulking

Percent Asbestos: Percent Non-Asbestos Fibrous Material: Percent Non-Fibrous Material:

None Detected None Detected

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017

Date Analyzed: 06/15/2017

Signature:

Analyst: Rodney Redman

Approved By:

Frank E. Ehrenfeld, III

Laboratory Director

Dated: 6/15/2017 5:25:38 PM Page 14 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd Report Date: 6/15/2017

16820 107 Ave Report No.: 538138 - PLM

Project: Asbestos Surveys - City of Saskatoon Edmonton AB T5P 4C3

Project No.: 1667963 Client: GOL572

Appendix to Analytical Report

Customer Contact:

Analysis: US EPA 600, R93-116

This appendix seeks to promote greater understanding of any observations, exceptions, special instructions, or circumstances that the laboratory needs to communicate to the client concerning the above samples. The information below is used to help promote your ability to make the most informed decisions for you and your customers. Please note the following points of contact for any questions you may have.

iATL Customer Service: customerservice@iatl.com

iATL Office Manager: cdavis@iatl.com iATL Account Representative: Pete Lesniak Sample Login Notes: See Batch Sheet Attached Sample Matrix: Bulk Building Materials **Exceptions Noted:** See Following Pages

General Terms, Warrants, Limits, Qualifiers:

General information about iATL capabilities and client/laboratory relationships and responsibilities are spelled out in iATL policies that are listed at www.iATL.com and in our Quality Assurance Manual per ISO 17025 standard requirements. The information therein is a representation of iATL definitions and policies for turnaround times, sample submittal, collection media, blank definitions, quantification issues and limit of detection, analytical methods and procedures, sub-contracting policies, results reporting options, fees, terms, and discounts, confidentiality, sample archival and disposal, and data interpretation.

iATL warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted. iATL disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. iATL accepts no legal responsibility for the purpose for which the client uses test results. Any analytical work performed must be governed by our Standard Terms and Conditions. Prices, methods and detection limits may be changed without notification. Please contact your Customer Service Representative for the most current information.

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA LAP LLC, or any agency of local, state or province governments nor of any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Information Pertinent to this Report:

Analysis by US EPA 600 93-116: Determination of Asbestos in Bulk Building Materials by Polarized Light Microscopy (PLM).

Certifications:

- NIST-NVLAP No. 101165-0
- NY-DOH No. 11021
- AIHA-LAP, LLC No. 100188

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analytical Methodology Alternatives: Your initial request for analysis may not have accounted for recent advances in regulatory requirements or advances in technology that are routinely used in similar situations for other qualified projects. You may have the option to explore additional analysis for further information. Below are a few options, listed as the matrix followed by the appropriate methodology. Also included are links to more information on our website.

Bulk Building Materials that are Non-Friable Organically Bound (NOB) by Gravimetric Reduction techniques employing PLM and TEM: ELAP 198.6 (PLM-NOB), ELAP 198.4 (TEM-NOB)

Loose Fill Vermiculite Insulation, Attic Insulation, Zonolite (copyright), etc.: US EPA 600 R-4/004 (multi-tiered analytical process) Sprayed On Insulation/Fireproofing with Vermiculite (SOF-V): ELAP 198.8 (PLM-SOF-V)>

Soil, sludge, sediment, aggregate, and like materials analyzed for asbestos or other elongated mineral particles (ex. erionite, etc.): ASTM D7521, CARB 435, and other options available

Dated: 6/15/2017 5:25:38 PM Page 15 of 16



9000 Commerce Parkway Suite B Mt. Laurel, New Jersey 08054 Telephone: 856-231-9449

Email: customerservice@iatl.com

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd Report Date: 6/15/2017

16820 107 Ave Report No.: 538138 - PLM

Edmonton AB T5P 4C3 Project: Asbestos Surveys - City of Saskatoon

Project No.: 1667963 Client: GOL572

Asbestos in Surface Dust according to one of ASTM's Methods (very dependent on sampling collection technique – by TEM): ASTM D 5755, D5756, or D6480

Various other asbestos matrices (air, water, etc.) and analytical methods are available.

Disclaimers / Qualifiers:

There may be some samples in this project that have a "NOTE:" associated with a sample result. We use added disclaimers or qualifiers to inform the client about something that requires further explanation. Here is a list with highlighted disclaimers that may be pertinent to this project. For a full explanation of these and other disclaimers, please inquire at customerservice@iatl.com.

- 1) Note: No mastic provided for analysis.
- 2) Note: Insufficient mastic provided for analysis.
- 3) Note: Insufficient material provided for analysis.
- 4) Note: Insufficient sample provided for QC reanalysis.
- 5) Note: Different material than indicated on Sample Log / Description.
- 6) Note: Sample not submitted.
- 7) Note: Attached to asbestos containing material.
- 8) Note: Received wet.
- 9) Note: Possible surface contamination.
- 10) Note: Not building material. 1% threshold may not apply.
- 11) Note: Recommend TEM-NOB analysis as per EPA recommendations.
- 12) Note: Asbestos detected but not quantifiable.
- 13) Note: Multiple identical samples submitted, only one analyzed.
- 14) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.080%.
- 15) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.125%.

Recommendations for Vermiculite Analysis:

Several analytical protocols exist for the analysis of asbestos in vermiculite. These analytical approaches vary depending upon the nature of the vermiculite mineral being tested (e.g. un-processed gange, homogeneous exfoliated books of mica, or mixed mineral composites). Please contact your client representative for pricing and turnaround time options available.

iATL recommends initial testing using the EPA 600/R-93/116 method. This method is specifically designed for the analysis of asbestos in bulk building materials. It provides an acceptable starting point for primary screening of vermiculite for possible asbestos.

Results from this testing may be inconclusive. EPA suggests proceeding to a multi-tiered analysis involving wet separation techniques in conjunction with PLM and TEM gravimetric analysis (EPA 600/R-04/004).

Further information on this method and other vermiculite and asbestos issues can be found at the following: Agency for Toxic Substances and Disease Registry (ATSDR) www.atsdr.cdc.gov, United States Geological Survey (USGS) www.minerals.usgs.gov/minerals/, US EPA www.epa.gov/asbestos. The USEPA also has an informative brochure "Current Best Practices for Vermiculite Attic Insulation" EPA 747F03001 May 2003, that may assist the health and remediation professional.

The following is a summary of the analytical process outlines in the EPA 600/R-04/004 Method:

1) Analytical Step/Method: Initial Screening by PLM, EPA 600R-93/116

Requirements/Comments: Minimum of 0.1 g of sample. ~0.25% LOQ for most samples.

2) Analytical Step/Method: Wet Separation by PLM Gravimetric Technique, EPA R-04/004 **Requirements/Comments:** Minimum 50g** of dry sample. Analysis of "Sinks" only.

3) Analytical Step/Method: Wet Separation by PLM Gravimetric Technique, EPA R-04/004 Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Floats" only.

4) Analytical Step/Method: Wet Separation by TEM Gravimetric Technique, EPA R-04/004 Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Sinks" only.

5) Analytical Step/Method: Wet Separation by TEM Gravimetric Technique, EPA R-04/004 Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Suspension" only.

LOQ, Limit of Quantitation estimates for mass and volume analyses.

*With advance notice and confirmation by the laboratory.

Dated: 6/15/2017 5:25:38 PM Page 16 of 16

^{**}Approximately 1 Liter of sample in double-bagged container (~9x6 inch bag of sample).



APPENDIX B

Site Photographs





Photograph 1: Asbestos-Containing Gold Sink Undercoat.

\\golder\gal\edmonton\active\2016\3 proj\1667963 cityofsaskatoon_asbsurveys_saskatoon\07 reports\04 - lawson heights cc and rml\appendix b - site photographs.docx





APPENDIX C

Room by Room Spreadsheet



Included/Ex cluded Floor	Room #	# Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing	Condition	Field Notes	Sample Type	Sample ID	Sample Asb		oduct % of a	sbestos Friab	e Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included All	All		Doors	Regular Door	Non Suspect Door	High	No	No	Material? No	Good	Non-suspect doors.	.,,,,,		5410 1,								Diotarbano	Audon			
Included All			Mechanical	Duct Work	Duct Connector Fabric	High	No	No	No	Good	The ceiling deck throughout the															
Included All Included B	B01	Mechanical Room	Ceiling Walls	Ceiling Walls	Ceiling Deck Concrete	Low High	No No	No No	No No	Good Good	Site was observed to be bare.															_
Included B Included B	B01	Mechanical Room Mechanical Room	Floor Ceiling	Floor Ceiling	Concrete Concrete	High High	No No	No No	No No	Good Good																
Included B	B01	Mechanical Room Mechanical Room	Mechanical	Duct Work Piping	Red/Brown Duct Mastic Pipe-Fitting Insulation	High High	No No	Yes Yes	No			Bulk	VS A-007 A-009	2- lun-17												
Included B	B01 HW	/ Mechanical Room	Walls	Walls	Concrete	High	No	No	No	Good		Duik	A-003	2-0011-17												
Included B	B01 HW	Mechanical Room Mechanical Room	Floor Ceiling	Floor Ceiling	Concrete Concrete	High High	No No	No No	No No																	
Included B	B02	Mechanical Room Mechanical Room	Walls	Duct Work Walls	Red/Brown Duct Mastic Concrete	High High	No No	Yes No	No	Good Good			VS A-007													
Included B Included B	B02 B02	Mechanical Room Mechanical Room	Floor Ceilina	Floor Ceiling	Concrete Concrete	High High	No No	No No	No No	Good Good																_
Included B Included B	B02 B03	Mechanical Room Hallway	Mechanical Walls	Piping Walls	Pipe-Fitting Insulation Concrete	High High	No No	Yes No	No No	Good Good			VS A-009													
Included B	B03	Hallway	Floor	Floor	Concrete	High	No No	No	No	Good																
Included B	B03		Ceiling Mechanical	Ceiling Piping	Concrete Drain Lines	High High	No	No No	No No	Good	PVC drain lines.		1.000	0.1.47												
Included B Included B	B03	Mechanical Room	Mechanical		Pipe-Fitting Insulation Red/Brown Duct Mastic	High High	No No	Yes Yes	No	Good Good		Bulk	A-008 VS A-007	2-Jun-17												
Included B Included B	B04 B04	Mechanical Room Mechanical Room	Walls Floor	Walls Floor	Concrete Concrete	High High	No No	No No		Good Good																
Included B Included B	B04 B04	Mechanical Room Mechanical Room	Ceiling Mechanical	Ceiling Duct Work	Concrete Red/Brown Duct Mastic	High High	No No	No Yes	No No	Good Good		Bulk	A-007	2-Jun-17												
Included B	B04	Mechanical Room Mechanical Room	Mechanical	Piping	Drain Lines	High	No	No	No	Good	PVC drain lines.															
Included B	DO4	Manharian Dans	Markariant	Dining	Disc Citize les detina	16-6	No	V	No	Good		D. II.	A-004, A-006, and A-006	0 hrs 47												
Included B	BU4	Mechanical Room	Wechanical	Piping	Pipe-Fitting Insulation	High	INO	Yes	INO	Good		Bulk	and A-006	Z=Jun=17												
				Electrical Panels and							Not sampled due to safety												Inspect and sample if scheduled for			
Included B Included B	B04 B05		Electrical Walls	Components Walls	Electrical Panels and Components Concrete	High High	Yes No	No No	Potential No	Good Good	concerns.						No	No		Annually		Low	removal.			
Included B Included B	B05	Hallway	Walls Floor	Walls Floor	Concrete Scratch Coat Concrete	High High	No No	Yes No	No No	Good Good		Bulk	A-002	2-Jun-17												
Included B	B05	Hallway	Ceiling Mechanical	Ceiling	Concrete	High	No No	No No	No No	Good Good	PVC drain lines.															
Included B Included B	B05	Hallway	Supplies	Piping Supplies	Drain Lines Loose Roll of Brown Vinyl Sheet Flooring with White and Dark Brown Flecks	High High	No No	Yes	No No	Good		Bulk	A-003	2-Jun-17												
Included B	B05	Hallway	Supplies	Supplies	Loose Roll of Beige Mosaic Vinyl Sheet Flooring	High	No	No	No	Good	Historically found to not contain asbestos.															
																							Inspect and sample			
Included B	B05	Hallway	Flectrical	Electrical Panels and Components	Electrical Panels and Components	High	Vac	No	Potential	Good	Not sampled due to safety						No	No		Appually		Low	if scheduled for removal.			
Included B	B05 SW	/ Stairwell	Walls	Walls	Block Wall	High	No No	No	No	Good	concerns.		A-001	0.1.47			140	NO		Aillually		LOW	Terriovai.			
Included B Included B	B05 SW	/ Stairwell	Walls Floor	Walls Floor	Concrete Scratch Coat Concrete	High High	No No	Yes No	No	Good		Bulk	A-001	Z=Jun=17												
Included B Included M Included M	B05 SW 101	Vestibule	Ceiling Walls	Ceiling Walls	Concrete Drywall Joint Compound	High High	No No	No Yes	No	Good Good			VS A-010													
Included M	101	Vestibule	Floor Ceiling	Floor Ceiling	Ceramic Tile Drywall Joint Compound	High High	No	No	No	Good Good			VS A-010													
Included M	101	Vestibule	Windows Walls	Windows Walls	Brown Window Frame Caulking Block Wall	High High	No No	Yes No	No	Good			VS A-011													
Included M Included M Included M	102	Lobby	Walls	Walls	Concrete Scratch Coat	High	No	Yes	No	Good			VS A-001													
included M	102	LODDY	Floor	Floor	Ceramic Tile	High	No	No	No	Good	Date coded to a time period in															
Included M	102	Lobby	Ceiling	Ceiling	2'x2' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	which asbestos use was not widespread.															
Included M Included M	102	Lobby	Windows Walls	Windows Walls	Brown Window Frame Caulking Block Wall	High High	No No	Yes No	No No				VS A-011													_
													A-035, A-036,													
Included M Included M	103	Library	Walls Floor	Walls Floor	Drywall Joint Compound Carpet	High High	No No	Yes No	No No	Good Good		Bulk	and A-037	2-Jun-17												4
Included M	103	Library	Floor	Floor	Ceramic Tile	High	No	No	No	Good																
											Date coded to a time period in which asbestos use was not															4
Included M Included M	103	Library	Ceiling Ceiling	Ceiling Ceiling	2'x2' Ceiling Tile with Small Pinholes and Small Divots 2'x4' Textured Ceiling Tile	High High	No No	No Yes	No No	Good Good	widespread.		VS A-022													_
Included M Included M	103	Library	Ceiling Windows	Ceiling Windows	2'x2' Ceiling Tile with a Square Pattern Grey Window Caulking	High High	No No	Yes Yes	No	Good Good		Bulk	A-038 A-044	2-Jun-17 2-Jun-17												
Included M Included M	103	Library		Piping	Pipe Insulation Duct Insulation	High High	No No	No	No	Good Good																
											i ibregiass insulation.	D. II	A-033 and A-													
Included M	104	Story Room Story Room		Walls Floor	Drywall Joint Compound Carpet	High High	No No	Yes No	No No No	Good Good		Bulk		2-Jun-17												
Included M Included M			Ceiling Walls	Ceiling Walls	2'x4' Textured Ceiling Tile Drywall Joint Compound	High High	No No	Yes Yes	No	Good			VS A-022 VS A-010													
Included M Included M Included M	Child WR	R Washroom	Floor Ceiling	Floor Ceiling	Beige Mosaic Vinyl Sheet Flooring 2'x4' Textured Ceiling Tile	High High	No No	Yes Yes	No	Good Good		Bulk	A-039 A-040	2-Jun-17 2-Jun-17												
Included M Included M	105	Activity Room	Walls Floor	Walls Floor	Drywall Joint Compound	High	No No	Yes Yes		Good			VS A-010 VS A-039													
Included M Included M	105	Activity Room	Ceiling	Ceiling	Beige Mosaic Vinyl Sheet Flooring 2'x4' Textured Ceiling Tile Gold Sink Undercoat	High High	No	Yes	No	Good Good		Bulk	A-041	2-Jun-17	entile Circle I	ercoat	0%	Ne	No	Annualli		Modorata	Manage in place.	1 Cint	Dhotogra-h 4	Door level
Included M	106	Staff Room	Plumbing Walls	Sink Walls	Drywall Joint Compound	High High	Yes No	Yes Yes	No	Good Good		BUIK	VS A-010	Z-Jun-17 Unry	Soure SINK UNG	ercoat 2.7	U70 INO	NO	INU	Annually	5	woderate	манауе іп ріасе.	I SINK	Enotograph 1	Door Jamb
Included M Included M Included M	106 106	Staff Room	Floor Ceiling	Floor Ceiling	Carpet 2'x4' Textured Ceiling Tile	High High	No No	No Yes	No No	Good Good			VS A-022													
Included M	107	Washroom	Plumbing Walls	Sink Walls	Gold Sink Undercoat Drywall Joint Compound	High High	Yes No		No				VS A-042 VS A-010		Sotile Sink Und	ercoat 2.7	0% No	No	No	Annually	5	Moderate	Manage in place.	1 Sink	Photograph 1	Door Jamb
Included M Included M	107	Washroom	Floor Ceiling	Floor Ceiling	Beige Mosaic Vinyl Sheet Flooring 2'x4' Textured Ceiling Tile	High High	No No	Yes Yes	No No				VS A-039 VS A-022													
Included M Included M	108	Washroom	Walls	Walls Floor	Drywall Joint Compound Beige Mosaic Vinyl Sheet Flooring	High	No No	Yes	No No	Good		Bulk	A-045 VS A-039	2-Jun-17												
Included M	108	Washroom	Floor Ceiling	Ceiling	2'x4' Textured Ceiling Tile	High High	No	Yes Yes	No	Good Good			VS A-022													
Included M Included M Included M	109	Hallway Hallway	Walls Floor	Walls Floor	Drywall Joint Compound Beige Mosaic Vinyl Sheet Flooring 2x4" Textured Ceiling Tile	High High	No No	Yes Yes	No No	Good			VS A-010 VS A-039													
Included M Included M	109 109	Hallway Hallway	Ceiling Mechanical	Ceiling Duct Work	2'x4' Textured Ceiling Tile Red/Brown Duct Mastic	High High	No No	Yes Yes	No No	Good Good		Bulk Bulk	A-043 A-049	2-Jun-17 2-Jun-17												
																							Inspect and sample			
Included M	109	Hallway	Flectrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.						No	No		Annually		Low	if scheduled for removal.			
Included M Included M	110	Vestibule	Walls	Walls	Drywall Joint Compound	High	No No	Yes	No No	Good	1150110.		VS A-010				.40			Juany						
Included M	110	Vestibule	Floor Ceiling	Floor Ceiling	Beige Mosaic Vinyl Sheet Flooring 2'x4' Textured Ceiling Tile	High High	No No	Yes Yes		Good			VS A-039 VS A-022													
Included M Included M	111	Book Storage	Walls Floor	Walls Floor	Drywall Joint Compound Beige Mosaic Vinyl Sheet Flooring	High High	No No	Yes Yes	No	Good Good		Bulk	A-046 VS A-039	2-Jun-17												
Included M Included M	111	Book Storage Office	Ceiling Walls	Ceiling Walls	2'x4' Textured Ceiling Tile Drywall Joint Compound	High High	No No	Yes Yes	No No	Good Good			VS A-022 VS A-010													
Included M	112	Office	Floor	Floor	Carpet 2'x4' Textured Ceiling Tile	High High	No No	No Yes	No	Good Good			VS A-022													
Included M Included M Included M	112	Office Office	Ceiling Windows Walls	Ceiling Windows Walls	Grey Window Caulking Drywall Joint Compound	High	No No	Yes	No No	Good			VS A-044 VS A-010													
Included M	113	Office	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring	High High	No	Yes Yes	No	Good			VS A-039													
Included M			Ceiling	Ceiling	2'x4' Textured Ceiling Tile	High	No	Yes	No				VS A-022 A-047 and A-													
Included M Included M	114 114	Office Office	Walls Floor	Walls Floor	Drywall Joint Compound Beige Mosaic Vinyl Sheet Flooring	High High	No No	Yes No	No No	Good Good		Bulk	048 VS A-039	2-Jun-17												
Included M	111	Office	Ceiling Windows	Ceiling Windows	2'x4' Textured Ceiling Tile Grey Window Caulking	High High	No No	Yes Yes	No	Good Good			VS A-022 VS A-044													
Included M Included M Included M	115	Classroom	Walls	Walls	Drywall Joint Compound	High High	No	Yes	No No	Good			VS A-010													
inciuded M	115	Uiassroom	Floor	Floor	Carpet	High	NO	INO	NO	G00d	I															

Included/Ex	r Room#	Area Descripti	on Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled	Asbestos Containing		Field Notes	Sample S		ple Asbestos	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection Pr	ority Potential for		Quantity Photograph I	ID Labelling Type
cluded							-		Material?		Date coded to a time period in	Туре	Da	te Type							Disturbance	Action		
Included M	115	Classroom	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	which asbestos use was not widespread.													
Included M	115	Classroom	Plumbing		Gold Sink Undercoat	High	Yes	Yes	Yes	Good			/S A-042 /S A-010	Chrysotile	Sink Undercoat	2.70%	No	No	No	Annually	5 Moderate	Manage in place.	1 Sink Photograph 1	1 Door Jamb
Included M Included M			Walls Floor	Floor	Drywall Joint Compound Carpet	High High	No No			Good Good		V	75 A-010											
											Date coded to a time period in which asbestos use was not													
Included M Included M	116 117	Coats Projector Room	Ceiling Walls	Ceiling Walls	2'x4' Ceiling Tile with Circular Patterned Fissures Drywall Joint Compound	High High	No No	No Yes	No No	Good Good	widespread.	V	/S A-010											_
Included M	117	Projector Room Projector Room	Floor	Floor	Carpet	High	No	No	No	Good	Date coded to a time period in													
Included M	117	Projector Poom	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	which asbestos use was not widespread.													
Included M	118	Projector Room Auditorium Auditorium	Walls	Walls	Drywall Joint Compound	High	No No	Yes		Good	widespread.	V	/S A-010											
included M	110	Auditorium	FIOOI	FIOOI	Carpet	High	NO	INO	INO	Good	Date coded to a time period in													
Included M			Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	which asbestos use was not widespread.													
Included M Included M	119 119	Storage Room Storage Room	Walls Floor	Walls Floor	Block Wall Beige Mosaic Vinyl Sheet Flooring	High High	No No			Good Good		V	/S A-039											_
											Date coded to a time period in which asbestos use was not													
Included M	119	Storage Room Custodian Office Custodian Office	Ceiling Walls	Ceiling Walls	2'x4' Ceiling Tile with Circular Patterned Fissures Block Wall	High High	No No	No No	No No	Good Good	widespread.													
Included M	120	Custodian Office	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring	High	No	Yes		Good	Date coded to a time period in	V	/S A-039											
	120	0 0"	0 77	0.17			No				which asbestos use was not													
Included M Included M	120	Custodian Office	Mechanical	Ceiling Piping	2'x4' Ceiling Tile with Circular Patterned Fissures Pipe-Fitting Insulation	High High	No				widespread.	V	/S A-009											
Included M Included M	121 121	Hallway Hallway	Walls Floor	Walls Floor	Block Wall Ceramic Tile	High High	No No	No No	No No	Good Good														
Included M Included M	121 122	Hallway	Ceiling Walls	Ceiling Walls	Concrete Scratch Coat Block Wall	High High	No No		No No	Good		V	/S A-001											_
Included M Included M	122	Washroom	Walls Floor	Walls Floor	Ceramic Tile Ceramic Tile	High High	No No	No No																
Included M Included M	122	Washroom	Ceiling Walls	Ceiling Walls	Concrete Scratch Coat Block Wall	High High	No No	Yes	No	Good		V	/S A-001											
Included M	123	Washroom	Floor	Floor	Ceramic Tile Concrete Scratch Coat	High	No No	No Yes					/S A-001											
Included M	124	Vestibule	Ceiling Walls	Ceiling Walls	Block Wall	High High	No	No	No	Good		V	75 A-001											
Included M Included M	124	Vestibule	Floor Ceiling	Floor Ceiling	Ceramic Tile Drywall Joint Compound	High High	No No	Yes					/S A-010											
Included M Included M	124 125	Vestibule Lobby	Windows Walls	Windows Walls	Brown Window Frame Caulking Block Wall	High High	No No	Yes No	No No	Good Good		V	/S A-011											_
Included M Included M	125 125	Lobby Lobby	Walls Floor	Walls Floor	Concrete Scratch Coat Ceramic Tile	High High	No No	Yes	No			V	/S A-001											
Included M Included M	125	Lobby	Ceiling Windows	Ceiling Windows	Metal Brown Window Frame Caulking	High High	No No	No	No				/S A-011											
Included M							No.	No.	No	Good	Suspected fibreglass insulation	·	75 A-011											
Included M	125	Lobby	Ceiling Mechanical	Soundproofing Piping	Fibreglass Panels at Heights Pipe-Fitting Insulation	High High	No	Yes	No	Good		V	/S A-009											
Included M Included M	126	Vestibule	Mechanical Walls	Duct Work Walls	Bare Duct Work Block Wall	High High	No No		No No		Uninsulated duct work.													
Included M Included M	126 126	Vestibule Vestibule	Floor Ceiling	Floor Ceiling	Ceramic Tile Drywall Joint Compound	High High	No No	No Yes	No No	Good		V	/S A-010											
Included M Included M	126 128	Vestibule Office	Windows Walls	Windows Walls	Brown Window Frame Caulking Drywall Joint Compound	High High	No No	Yes Yes		Good Good			/S A-011 /S A-010											
Included M			Floor	Floor	Carpet	High	No				Date coded to a time period in													
Included M	128	Office	Coiling	Cailing	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	which asbestos use was not widespread.													
Included M	129	Office	Ceiling Walls	Ceiling Walls	Drywall Joint Compound	High	No	Yes	No	Good		V	/S A-010											
Included M	129	Office	Floor	Floor	Carpet	High	No	No	No	Good	Date coded to a time period in													
Included M	129	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	which asbestos use was not widespread.													
Included M Included M	130 A/B/C 130 A/B/C	I/D Office	Walls Walls	Walls Walls	Drywall Joint Compound Block Wall	High High	No No	Yes No	No No			Bulk	A-028 2-Ju	n-17										_
Included M	130 A/B/C	C/D Office	Floor	Floor	Carpet	High	No	No	No	Good		A-(029 and A-											
Included M Included M	130 A/B/C		Ceiling Windows	Ceiling Windows	2'x4' Textured Ceiling Tile Black Window Caulking	High High	No No	Yes Yes	No No	Good Good			030 2-Ju	n-17										
Included M Included M	131	Waiting Area	Walls Floor	Walls Floor	Block Wall Ceramic Tile	High	No No	No	No	Good		Duik	A-031 2-00	1-17										
Included M	131	Waiting Area	Ceiling	Ceiling	Drywall Joint Compound	High High	No	Yes	No	Good			/S A-010 /S A-011											
Included M Included M	131A	Janitor Room	Doors Walls	Doors Walls	Brown Door Frame Caulking Block Wall	High High	No No	No	No	Good		V	7S A-011											
Included M Included M	131A 131A	Janitor Room Janitor Room	Floor Ceiling	Floor Ceiling	Concrete Drywall Joint Compound	High High	No No	No Yes				Bulk	A-026 2-Ju	n-17										
																						Inspect and sample		
Included M	131A	Janitor Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.						No	No		Annually	Low	if scheduled for removal.		
Included M	132	Janitor Room	Walls Floor	Walls Floor	Block Wall Ceramic Tile	High High	No No	No No	No No	Good														
Included M Included M	132	Janitor Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-027 2-Ju	n-17										
				Electrical Develo							Not sampled due to safety											Inspect and sample if scheduled for		
Included M		Janitor Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential		concerns.						No	No		Annually	Low	removal.		
Included M Included M	133	Janitor Room	Walls Floor	Walls Floor	Block Wall Concrete	High High	No	No	No															
Included M Included M	133 134	Janitor Room Concession	Ceiling Walls	Ceiling Walls	Drywall Joint Compound Block Wall	High High	No No	Yes No	No	Good		V	/S A-010											
Included M Included M Included M	134	Concession	Floor Ceiling	Floor Ceiling	Ceramic Tile Drywall Joint Compound	High High	No No	No	No			V	/S A-010											
Included M	134	Concession	Doors Walls	Doors Walls	Brown Door Frame Caulking Concrete Scratch Coat	High	No No					V	/S A-011 /S A-001											
Included M Included M Included M	135	Dining Area	Floor	Floor Ceiling	Ceramic Tile	High High High	No No	No	No No	Good		· ·												
Included M	135	Dining Area	Ceiling Mechanical	Duct Work	Bare Duct Work	High High	No	No	No	Good			(C. A. 004											
Included M Included M Included M	136 136	Seating Area Seating Area	Walls Walls	Walls Walls	Concrete Scratch Coat Block Wall	High High	No No					V	/S A-001											
Included M Included M	136 136	Seating Area Seating Area	Floor Ceiling	Floor Ceiling	Ceramic Tile Metal	High High	No No			Good Good														
Included M	136	Seating Area	Ceiling	Soundproofing	Fibreglass Panels at Heights	High	No	No	No	Good	Suspected fibreglass insulation panels at heights.													
Included M Included M	136 136	Seating Area Seating Area	Mechanical Mechanical	Piping	Pipe-Fitting Insulation Bare Duct Work	High High	No No	Yes No	No No	Good Good		V	/S A-009											
Included M	137	Seating Area	Walls	Walls Floor	Concrete Scratch Coat Ceramic Tile	High	No No	No	No	Good	SSudiou dust Work.	V	/S A-001											
Included M	137	Seating Area Seating Area Seating Area Seating Area Seating Area Pool Administratio	Ceiling	Ceiling	Metal	High High	No	No	No	Good														
Included M Included M	137	Seating Area Seating Area	Mechanical Windows	Duct Work Windows	Bare Duct Work Brown Window Frame Caulking	High High	No No	No Yes	No	Good Good	Uninsulated duct work.	V	/S A-011											
Included M	138	Pool Administratio	n Walls	Walls Walls	Block Wall Drywall Joint Compound	High High	No No	Yes	No			Bulk	A-020 2-Ju	n-17										
Included M	138	Pool Administratio	n Floor	Floor	Ceramic Tile	High	No				Date coded to a time period in													
Included M	139	Pool Administration	n Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	which asbestos use was not widespread.													
Included M	138	Pool Administratio Pool Administratio Pool Administratio	n Mechanical	Duct Work	2x4 Ceiling Tile With Circular Patterned Pissures Bare Duct Work Brown Window Frame Caulking	High	No	No	No	Good	Uninsulated duct work.		/S A-011											
Included M	138	Pool Administratio Pool Administratio	n Mechanical	Duct Work	Red/Brown Duct Mastic	High High	No No	Yes Yes	No No	Good Good Good	-		/S A-011 /S A-007											
Included M Included M	138 139	Poor Administratio	n Mechanical Walls	Piping Walls	Pipe Insulation Drywall Joint Compound	High High	No No	No No	No No	Good Good	Fibreglass insulation.	V	/S A-010											

Included/Ex									Asbestos			Sample	Sample Sample	Asbestos						Potential for	Recommended		
		om # Area Description	on Elements		Material Description	Accessibility		, N	Material?	Condition	Field Notes	Type	Date	Type	ACM Product	% of asbestos	Friable Sprayed-	on Maintenance	Inspection Priority	Disturbance	Action	Quantity Photograph	ID Labelling Type
Included M Included M Included M	1	39 Office 39 Office	Floor Ceiling Walls	Floor Ceiling Walls	Grey and Blue Speckled Vinyl Sheet Flooring 2'x4' Textured Ceiling Tile Drywall Joint Compound	High High	No No No	Yes	No No	Good Good			A-021 2-Jun-17 A-022 2-Jun-17 VS A-010										
Included M	1	40 Office	Floor	Floor	Grey and Blue Speckled Vinyl Sheet Flooring	High High	No	No Yes	No	Good			VS A-021 A-023 and A-										
Included M Included M Included M	1	40 Office 41 Hallway	Ceiling Walls	Ceiling Walls	2'x4' Textured Ceiling Tile Block Wall	High High	No No	Yes No	No No	Good Good		Bulk	024 2-Jun-17										_
Included M	1	41 Hallway	Walls Walls Floor	Walls Floor	Concrete Scratch Coat Ceramic Tile	High High	No No	Yes No	No	Good Good			VS A-001										
Included M Included M	1	41 Hallway 42 Washroom 42 Washroom	Ceiling Walls Floor	Ceiling Walls Floor	Concrete Scratch Coat Ceramic Tile Ceramic Tile	High High	No No No	No	No	Good Good Good		Bulk	A-019 2-Jun-17										
Included M	1	42 Washroom	Ceiling Walls	Ceiling Walls	Concrete Scratch Coat Plastic Panels	High High High	No No	Yes No		Good Good			VS A-001										_
Included M Included M	1	43 Change Room 43 Change Room 43 Change Room 44 Change Room	Floor Ceiling	Floor Ceiling	Ceramic Tile Plastic Panels	High High	No No	No No	No No	Good Good													
Included M	1	44 Change Room	Walls Floor	Walls Floor	Plastic Panels Ceramic Tile	High High	No No			Good Good													
Included M	1-	44 Change Room 45 Change Room	Ceiling Walls	Ceiling Walls	Plastic Panels Plastic Panels	High High	No No	No No	No No	Good Good													
Included M Included M	1-	45 Change Room 45 Change Room 46 Shower	Floor Ceiling	Floor Ceiling	Ceramic Tile Plastic Panels	High High	No No	No No	No No	Good Good Good													
Included M Included M	1	46 Shower 46 Shower 46 Shower	Walls Floor Ceiling	Walls Floor Ceiling	Ceramic Tile Ceramic Tile Concrete Scratch Coat	High High High	No No No	No No Yes	No No	Good			VS A-001										
Included M Included M	1-	47 Locker Room 47 Locker Room	Walls	Walls Floor	Block Wall Ceramic Tile	High High	No No	No No	No No	Good			1071.001										
Included M Included M	1	47 Locker Room 48 Dry Off Area	Ceiling Walls	Ceiling Walls	Concrete Scratch Coat Block Wall	High High	No No	Yes No		Good Good		Bulk	A-018 2-Jun-17										
Included M Included M	1	48 Dry Off Area 48 Dry Off Area 48 Dry Off Area	Walls Floor	Walls Floor	Ceramic Tile Ceramic Tile	High High	No No	No No	No	Good Good													
Included M	1-	49 Washroom	Ceiling Walls	Ceiling Walls	Concrete Scratch Coat Block Wall	High High	No No	Yes No		Good			VS A-001										
	1	49 Washroom 49 Washroom 49 Washroom	Walls Floor Ceiling	Walls Floor Ceiling	Ceramic Tile Concrete Scratch Coat	High High High	No No No	No No Yes	No No	Good Good			VS A-001										
Included M Included M	1	50 Washroom 50 Washroom	Ceiling Walls Walls	Ceiling Walls Walls	Concrete Scratch Coar Block Wall Ceramic Tile	High High High	No No		No	Good Good			. 37. 331										
Included M Included M	1	50 Washroom 50 Washroom	Floor Ceiling Walls	Floor Ceiling	Ceramic Tile Concrete Scratch Coat	High High	No No	No Yes	No No	Good Good		Bulk	A-017 2-Jun-17										
Included M Included M	1	51 Dry Off Area 51 Dry Off Area	Floor	Walls Floor	Ceramic Tile Ceramic Tile	High High	No No	No No	No No	Good Good													
Included M	1	51 Dry Off Area 52 Shower	Ceiling Walls	Ceiling Walls	Concrete Scratch Coat Ceramic Tile	High High	No No	No	No	Good Good			VS A-001										
Included M Included M	1	52 Shower 52 Shower	Floor Ceiling	Floor Ceiling	Ceramic Tile Concrete Scratch Coat	High High	No No	No Yes	No No	Good			VS A-001										
Included M Included M	1	53 Locker Room	Walls Floor	Walls Floor	Block Wall Ceramic Tile Congrete Secretch Cont	High High	No No	No No	No No	Good Good			VC A 004										
Included M Included M Included M	1	53 Locker Room 54 Hallway 54 Hallway	Ceiling Walls Floor	Ceiling Walls Floor	Concrete Scratch Coat Block Wall Ceramic Tile	High High High	No No No	Yes No No	No No	Good Good			VS A-001										
Included M Included M	1	54 Hallway 54 Hallway	Ceiling Ceiling	Ceiling Ceiling	Drywall Joint Compound Concrete	High High	No No	Yes No	No No	Good		Bulk	A-010 2-Jun-17										
Included M	1	54 Hallway 55 Fitness Room 55 Fitness Room	Mechanical Walls	Duct Work Walls	Red/Brown Duct Mastic Block Wall	High High	No No	Yes No	No No	Good Good			VS A-007										
Included M Included M	1	55 Fitness Room 55 Fitness Room	Walls Floor	Walls Floor	Drywall Joint Compound Beige Rubber	High High	No No	Yes No		Good Good	Non-suspect flooring.		VS A-010										
											Date coded to a time period in which asbestos use was not												
Included M Included M Included M	1	55 Fitness Room 55 Fitness Room	Ceiling Doors	Ceiling Doors	2'x'4 Ceiling Tile with Circular Patterned Fissures Brown Door Frame Caulking	High High	No No	No Yes	No No	Good	widespread.	Bulk	A-011 2-Jun-17										
Included M	1	55 Fitness Room	Mechanical Windows	Duct Work Windows Walls	Red/Brown Duct Mastic Rubber Window Caulking Wood	High High	No No	Yes No	No	Good			VS A-007										
Included M Included M Included M	1 1	 56 Sauna 56 Sauna 56 Sauna 	Walls Floor Ceiling	Floor Ceiling	wood Ceramic Tile Wood	High High High	No No No	No No Yes	No No	Good Good													_
Included M	1		Windows	Windows Walls	Rubber Window Caulking Block Wall	High High	No No	No	No	Good													_
Included M	1	57 Storage Room	Floor Ceiling	Floor Ceiling	Beige Mosaic Vinyl Sheet Flooring Metal	High High	No No	Yes Yes		Good Good			VS A-039										
Included M Included M Included M	1	57 Storage Room	Mechanical Mechanical	Piping Duct Work	Pipe Insulation Duct Insulation	High High	No No	No No	No No	Good Good	Fibreglass insulation. Fibreglass insulation.												
Included M Included M	1	58 Chlorine Room 58 Chlorine Room	Walls Floor	Walls Floor	Block Wall Concrete	High High	No No		No	Good Good													
Included M	- 1	58 Chlorine Room 58 Chlorine Room	Ceiling Mechanical Walls	Ceiling Duct Work Walls	Drywall Joint Compound Red/Brown Duct Mastic Concrete Scratch Coat	High High	No No No	Yes Yes	No	Good Good			VS A-010 VS A-007 A-015 2-Jun-17										
Included M	1	 Indoor Playground Indoor Playground Indoor Playground 	Floor	Floor Floor	Rubber Ceramic Tile	High High	No No	Yes No No	No	Good Good	Non-suspect flooring.	DUIK	A-015 2-Jun-17										
Included M	1	59 Indoor Playground	Ceiling	Ceiling	Metal Bare Duct Work	High High High	No	Yes	No	Good	Uninsulated duct work												
Included M	1	59 Indoor Playground 60 Pool 60 Pool	Floor	Floor	Concrete Scratch Coat Ceramic Tile	High High	No No	Yes No	No No	Good Good	Uninsulated duct work. Non-suspect flooring.	Bulk	A-016 2-Jun-17										
Included M	1	60 Pool	Ceiling	Ceiling	Metal	High	No	No	No	Good	Suspected fibreglass insulation												
Included M Included M Included M	1	C4 Hallinger	Ceiling Walls	Soundproofing Walls	Fibreglass Panels at Heights Block Wall	High High	No No			Good Good	panels at heights.												
Included M Included M Included M Included M	1	61 Hallway 61 Hallway	Floor Ceiling Ceiling	Floor Ceiling Ceiling	Ceramic Tile Drywall Joint Compound Concrete	High High High	No No No	No Yes No		Good Good		Bulk	A-025 2-Jun-17										
Included M	1	61 Hallway	Ceiling Windows Windows	Windows Windows	Brown Window Frame Caulking Rubber Window Caulking	High High High	No No	Yes No	No No	Good Good			VS A-011										
Included M Included M	1	62 Storage Room 62 Storage Room	Walls Floor	Walls Floor	Block Wall Concrete	High High	No No	No	No	Good Good													
Included M Included M	1	62 Storage Room 62 Storage Room	Ceiling Mechanical	Ceiling Piping	Metal Pipe-Fitting Insulation	High High	No No	No Yes	No No	Good Good			VS A-009										
			Walle	Walls Floor	Block Wall Concrete	High High	No No	No No	No No	Good Good													
Included M Included M	1	63 Mechanical Room 63 Mechanical Room 63 Mechanical Room	Ceiling Mechanical	Ceiling Piping	Metal Pipe-Fitting Insulation	High High	No No	No Yes	No	Good		D. F	VS A-009										
Included M	1	63 Mechanical Room 64 Washroom 64 Washroom	Windows Walls Floor	Windows Walls Floor	Grey Window Frame Caulking Block Wall Ceramic Title	High High High	No No No		No	Good Good Good		BUIK	A-014 2-Jun-17										
Included M	- 1	64 Washroom 65 Janitor Room	Ceiling Walls	Ceiling Walls	Drywall Joint Compound Block Wall	High High	No No	Yes No	No	Good Good			VS A-010										
Included M	1	65 Janitor Room 65 Janitor Room 65 Janitor Room	Walls Floor	Walls Floor	Drywall Joint Compound Beige Mosaic Vinyl Sheet Flooring	High High	No No	Yes Yes	No No	Good Good		Bulk Bulk	A-012 2-Jun-17 A-013 2-Jun-17										
Included M	1	65 Janitor Room	Ceiling	Ceiling	Metal	High	No	No	No	Good													
				Electrical Panels and	1						Not sampled due to safety										Inspect and sample if scheduled for		
Included M Included M	- 1	65 Janitor Room 66 Open Area	Electrical Walls	Components Walls	Electrical Panels and Components Block Wall	High High	Yes No	No	No	Good Good	concerns.						No No		Annually	Low	removal.		
Included M Included M	1	66 Open Area 66 Open Area 66 Open Area	Floor Ceiling Mechanical	Floor Ceiling Duct Work	New Green Vinyl Sheet Flooring Metal Bare Duct Work	High High	No No	INO	No	Good Good	Non-suspect flooring.												
Included M	1	66	Mechanical Mechanical Walls		Bare Duct Work Pipe-Fitting Insulation Block Wall	High High High	No No No	Yes	No				VS A-009										
Included M	167	7/168 Change Room	Floor Ceiling	Floor Ceiling	Biock wall Rubber Flooring Metal	High High	No No			Good Good	Non-suspect flooring.												
Included M	1	7/168 Change Room 7/168 Change Room 69 Change Room	Mechanical Walls	Piping Walls	Pipe-Fitting Insulation Block Wall	High High	No No	Yes No	No No	Good Good		Bulk	A-032 2-Jun-17										
to alcord and 8.4		CO Characa Danas	Floor Ceiling Mechanical	Floor Ceiling	Rubber Flooring Metal	High High	No No	No No	No No	Good	Non-suspect flooring.												
Included M Included M	1	69	Mechanical Mechanical	Piping	Pipe-Fitting Insulation Bare Duct Work	High High	No No	Yes No	No	Good			VS A-009										

Included/E	Floor	Room #	Area Description	n Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos F	riable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	M	170	Change Room	Walls	Walls	Block Wall	High	No	No	No	Good																	
Included	M	170	Change Room	Floor	Floor	Concrete	High	No	No	No	Good	Non-suspect flooring.																
Included	M	170	Change Room	Ceiling Mechanical	Ceiling	Metal	High	No	No	No	Good																	
Included	M		Change Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good			VS A-009														
Included	M	170	Change Room	Mechanical	Duct Work	Bare Duct Work	High	No	No	No	Good																	
																									Inspect and sample			
					Electrical Panels and	i l						Not sampled due to safety													if scheduled for			
Included	M	170	Change Room	Electrical	Components	Electrical Panels and Components	High	Yes	No	Potential	Good	concerns.							No	No		Annually		Low	removal.			
Included	S	201	Mechanical Room	Walls	Walls	Block Wall	High	No	No	No	Good																	
Included	S	201	Mechanical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	S	201	Mechanical Room	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
														A-050 and A-														
Included	S	201	Mechanical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	051	2-Jun-17													
Included	S	201	Mechanical Room	Mechanical	Duct Work	Bare Duct Work and Fibreglass Insulation	High	No	No	No	Good	Non-suspect duct insulation.																
Included	S	201	Mechanical Room	Mechanical	Firestop	Red Firestop	High	No	Yes	No	Good		Bulk		2-Jun-17													
Included	S	201	Mechanical Room	Mechanical	Duct Work	Red/Brown Duct Mastic	High	No	Yes	No	Good	Painted white.		VS A-007														
																									Inspect and sample			
					Electrical Panels and	i l						Not sampled due to safety													if scheduled for			
Included	S	201	Mechanical Room	Electrical	Components	Electrical Panels and Components	High	Yes	No	Potential	Good	concerns.							No	No		Annually		Low	removal.			
																									Inspect and sample			
					Boilers and							Not sampled due to safety													if scheduled for			
Included	S	201	Mechanical Room	Mechanical	Components	Boilers and Components	High	Yes	No	Potential		concerns.							No	No		Annually		Low	removal.			
Included	S	202B	Mechanical Room	Walls	Walls	Block Wall	High	No	No	No	Good																	
														A-053, A-054,														
Included	S	202B	Mechanical Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	and A-055	2-Jun-17													
Included	S	202B	Mechanical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	S		Mechanical Room	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included		202B	Mechanical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-056	2-Jun-17													
Included			Mechanical Room	Mechanical	Duct Work	Bare Duct Work and Fibreglass Insulation	High	No		No	Good	Non-suspect duct insulation.																
Included	S	202B	Mechanical Room	Mechanical	Duct Work	Red/Brown Duct Mastic	High	No	Yes	No	Good	Painted white.		VS A-007														
											1			A-057, A-058,														
											1			A-059, A-060,														
														A-061, A-062,														
Included	E	Exterior	Exterior	Walls	Walls	Stucco	High	No	Yes	No	Good		Bulk	and A-063	2-Jun-17													
											1			A-064, A-065,	,													
											1			A-066, A-067,	,													
											1			A-068, A-069,														
Included	E	Exterior		Walls	Walls	Brick Mortar	High	No	Yes	No	Good		Bulk	and A-070	2-Jun-17													
Included		Exterior		Walls	Walls	Red/Brown Building Caulking	High	No	Yes	No	Good		Bulk	A-071	2-Jun-17													
Included		Exterior		Walls	Walls	Grey Building Caulking	High	No	Yes	No	Good		Bulk	A-072	2-Jun-17													
Excluded	M	202A	Office	Entire Room	Entire Room							Access was not provided.																
												Not assessed due to scope of																
Excluded		Exterior	Roof	Exterior Roof	Exterior Roof							work.																



APPENDIX D

Floor Plans



- 1. ASBESTOS IS A CARCINOGEN. DO NOT BREATHE ASBESTOS DUST.
- 2. SAMPLES A-057 TO A-072 WERE COLLECTED ALONG THE EXTERIOR OF THE BUILDING.

CITY OF SASKATOON

CONSULTANT

YYYY-MM-DD	2017-07-11
DESIGNED	КН
PREPARED	YAW
REVIEWED	КН
APPROVED	AG

SCHEMATIC ONLY, NOT TO SCALE


ASBESTOS ASSESSMENT

LAWSON HEIGHT CIVIC CENTRE AND RUSTY MacDONALD LIBRARY 225 PRIMROSE DRIVE

LOWER FLOOR

_	PROJECT NO.	CONTROL	REV.	FIGURE
	1667963	1000-HM-0002	0	1

PLAN OBTAINED FROM INFRASTRUCTURE SERVICES DEPARTMENT CITY OF SASKATOON. DATED: JULY 11, 2003.



NOTE(S)

- 1. ASBESTOS IS A CARCINOGEN. DO NOT BREATHE ASBESTOS DUST.
- SAMPLES A-057 TO A-072 WERE COLLECTED ALONG THE EXTERIOR OF THE BUILDING.

LEGEND

ASBESTOS - CONTAINING SINK UNDERCOAT

REFERENCE(S)

PLAN OBTAINED FROM INFRASTRUCTURE SERVICES DEPARTMENT CITY OF SASKATOON. DATED: 11/08/2011.

CLIENT

CITY OF SASKATOON

CONSULTANT

YYYY-MM-DD

2017-07-11

DESIGNED

KH

PREPARED

YAW

REVIEWED

KH

APPROVED

AG

CT

ASBESTOS ASSESSMENT

LAWSON HEIGHT CIVIC CENTRE AND RUSTY MacDONALD LIBRARY 225 PRIMROSE DRIVE

TITLE

MAIN FLOOR

PROJECT NO.	CONTROL	REV.	FIGURE
1667963	1000-HM-0003	0	2

25 mm

NOTE(S)

- ASBESTOS IS A CARCINOGEN. DO NOT BREATHE ASBESTOS DUST.
- SAMPLES A-057 TO A-072 WERE COLLECTED ALONG THE EXTERIOR OF THE BUILDING.

LEGEND

NO ACCESS

REFERENCE(S)

PLAN OBTAINED FROM INFRASTRUCTURE SERVICES DEPARTMENT CITY OF SASKATOON. DATED: 09/07/1999.

CLIEN

CITY OF SASKATOON

CONSULTANT



YYYY-MM-DL	2017-07-11
DESIGNED	КН
PREPARED	YAW
REVIEWED	КН
APPROVED	AG

SCHEMATIC ONLY, NOT TO SCALE

PROJECT

ASBESTOS ASSESSMENT

LAWSON HEIGHT CIVIC CENTRE AND RUSTY MacDONALD LIBRARY

225 PRIMROSE DRIVE

TITLE

SECOND FLOOR

•	1667963	1000-HM-0004	0 0	3
	DDO IECT NO	CONTROL	REV.	FIGURE

25 mm IT THIS IMEAS ONE WENT DOES NO

As a global, employee-owned organisation with over 50 years of experience, Golder Associates is driven by our purpose to engineer earth's development while preserving earth's integrity. We deliver solutions that help our clients achieve their sustainable development goals by providing a wide range of independent consulting, design and construction services in our specialist areas of earth, environment and energy.

For more information, visit golder.com

Africa + 27 11 254 4800 Asia + 86 21 6258 5522 Australasia + 61 3 8862 3500 Europe + 356 21 42 30 20 North America + 1 800 275 3281 South America + 56 2 2616 2000

solutions@golder.com www.golder.com

Golder Associates Ltd. 16820 107 Avenue Edmonton, Alberta, T5P 4C3 Canada T: +1 (780) 483 3499



Bersch Consulting Ltd.

August 28, 2019

City of Saskatoon 3130 Laurier Drive Saskatoon, SK S7L 5J7

ATTENTION: Brent Anderson

SUBJECT: Bulk Sample Analysis Report

Please find attached the laboratory results for the bulk samples collected on August 20, 2019 from the Lawson Civic Centre in Saskatoon, Saskatchewan. The samples were analyzed for the identification of asbestos. Asbestos <u>was not</u> detected within any of the samples.

The results for the samples submitted were obtained by examination in accordance with the current USEPA 600/R-93/116 Method for the analysis of asbestos in building materials using polarized light microscopy and dispersion staining techniques. The detection limit of this method is listed as less than 1% by volume.

This test report relates only to the materials sent for examination and any use or extension of the information by the client of these results is the responsibility of the client.

If any questions arise on the results of the attached information, please contact our office. Thank you for this opportunity of service.

Sincerely,

Tyneal Knackstedt
Bersch Consulting Ltd.

B67BLH20I-Lawson Civic Centre

Bersch Consulting Ltd.

Bulk Sample Analysis Report

August 28, 2019

Project Number: B67.19

Client: City of Saskatoon

Contact: Brent Anderson

Location: Lawson Civic Centre

File Number: B67BAH20I

Sample Number	Sample Date	Sample Material	Sample Location and Information	Asbestos	%	Analyst
1 a	2019/08/20	Grey/Black roof shingle	Roof surface beneath air units	No asbestos detected		EMSL/WB
1b	2019/08/20	Black roof membrane	Roof surface beneath air units	No asbestos detected		EMSL/WB
2	2019/08/20	Grey caulking	Between conduit and curb	No asbestos detected		EMSL/WB
3	2019/08/20	Beige caulking	Between air unit and curb	No asbestos detected		EMSL/WB

Note: The results for the samples submitted were obtained by examination in accordance with the current USEPA 600/R-93/116 Method for the analysis of asbestos in building materials using polarized light microscopy and dispersion staining techniques. The detection limit of this method is listed as less than 1% by volume.

Site Photos

Photo ID

B67BLH20I - 001

Sample Number

B67BAH20I - 1a

Description

Grey/Black Roof Shingle.

Roof Surface Beneath Air Units.



Photo ID

B67BLH20I - 002

Sample Number

B67BAH20I - 1b

Description

Black Roof Membrane.

Roof Surface Beneath Air Units.



Photo ID

B67BLH20I - 003

Sample Number

B67BAH20I - 2

Description

Grey Caulking.

Between Conduit and Curb.



Photo ID

B67BLH20I - 004

Sample Number

B67BAH20I - 3

Description

Beige Caulking.

Between Air Unit and Curb.

