



July 11, 2017

CITY OF SASKATOON

Asbestos-Containing Building Materials Assessment Report - Sasktel Centre



Submitted to:

The City of Saskatoon
1101 Avenue P North
Saskatoon, SK S7L 7K6

Report Number: 1667963

Distribution:

One Copy: City of Saskatoon
One Copy: Golder Associates Ltd.

REPORT





Table of Contents

1.0 INTRODUCTION.....	1
2.0 SCOPE OF WORK	1
2.1 Asbestos-Containing Materials	1
3.0 RESULTS AND DISCUSSION	2
3.1 Asbestos-Containing Materials	2
3.1.1 List of Identified Asbestos-Containing Materials	2
3.1.2 Non Asbestos-Containing Materials	4
4.0 EXCLUDED AREAS AND MATERIALS	5
5.0 CONCLUSIONS AND RECOMMENDATIONS.....	6
5.1 Asbestos-Containing Materials	6
6.0 SURVEY LIMITATIONS.....	7
7.0 CLOSURE.....	8
 APPENDICES	
APPENDIX A	
Laboratory Certificate of Analysis Report	
APPENDIX B	
Site Photographs	
APPENDIX C	
Room by Room Spreadsheet	
APPENDIX D	
Floor Plans	



1.0 INTRODUCTION

Golder Associates Ltd. (Golder) was retained by the City of Saskatoon (the Client) to conduct an asbestos-containing building materials assessment of the Sasktel Centre (the Site) located at 3515 Thatcher Avenue in Saskatoon, Saskatchewan. This assessment report details our findings, conclusions and recommendations for the Site. A walkthrough of the Site was conducted on February 22, 2017 and the assessment was conducted on May 29, 30, and 31, 2017 by Kody Henderson, OHS Project Manager, and Heather Tweedie, Junior Scientist/OHS Technologist. Asbestos-containing building materials were identified within the Sasktel Centre during the assessment. Further information is provided in Section 3.0.

2.0 SCOPE OF WORK

In accordance with Tender 16-0844, Golder's scope of work included conducting an asbestos-containing building materials assessment of the Site to evaluate the quantities, locations, and conditions of asbestos-containing building materials.

Following the field work, Golder prepared this assessment report that includes laboratory analysis results, findings of the assessment, conclusions, and recommendations.

2.1 Asbestos-Containing Materials

The assessment involved a non-destructive inspection of the Site to assess the type and extent of suspect ACMs in the facility. The systems that were reviewed as part of the inspections included, but were not limited to:

- *Structural* - systems including: insulation between solid webbed joists, fireproofing, building envelope, and interior/exterior caulking around windows and doors;
- *Mechanical* - systems insulation including: hot water and steam system, condensate system, chilled water system, glycol system, domestic hot and cold water, emergency generator exhaust, boiler units, heat exchangers, and asbestos cement piping; and
- *Architectural* - systems including: texture coats, sheet flooring, vinyl floor tile, acoustical spray-applied materials, condensation control applications, ceiling tile, wall board, drywall joint compound, and asbestos sheet products.

Systematic sampling of suspect ACMs was conducted as part of the assessment. Samples were submitted under chain of custody to International Asbestos Testing Laboratory Inc. (IATL) and analyzed for asbestos type and percentage content using Polarized Light Microscopy (PLM) in accordance with EPA methodologies (EPA 600/R-93/116).

Further information related to the assessment and sample collection methods can be found in the Golder document *Golder Asbestos Assessment General Survey Plan and Protocol* provided to the Client.



3.0 RESULTS AND DISCUSSION

The Sasktel Centre was constructed in 1987 and consists of an arena level, mezzanine level, concourse level, and gondola level. Various mechanical and electrical rooms, washrooms, maintenance offices, change rooms and concessions/kitchens are located on the arena level as well as the arena floor itself. The mezzanine and concourse levels consists of multiple washrooms, concessions/kitchens, suites, mechanical rooms, and offices. The gondola level consists mainly of offices and suites.

Numerous renovations have occurred within the offices, suites, and concessions/kitchens located throughout the Site. Each level was treated as its own functional space, and within each level, the inner and outer rooms were treated as separate functional spaces.

- The Laboratory Certificate of Analysis report for the bulk asbestos samples is included in Appendix A.
- Photographs collected during the assessment are provided in Appendix B.
- A room by room spreadsheet outlining the locations, quantities, friability, and condition of identified asbestos-containing materials as well as additional information is provided in Appendix C.
- A floor plan outlining the sample locations and locations of identified asbestos-containing materials is provided in Appendix D.
- Please refer to Sections 4.0 and 6.0 of this report for a summary of the limitations encountered.

3.1 Asbestos-Containing Materials

A total of one hundred and nine (109) samples of building materials were collected and tested for asbestos content during the assessment of the Lions Arena. Four (4) of the samples were found to contain asbestos.

3.1.1 List of Identified Asbestos-Containing Materials

A list of the identified asbestos-containing materials is below.

- Gold/Silver Sink Undercoat;
- Red/Brown Duct Mastic; and
- Black Interior Window Caulking (select rooms only).

Further information on the identified asbestos-containing materials listed is provided below.

Gold/Silver Sink Undercoat

One (1) sample of gold/silver sink undercoat was collected during the assessment. The sample collected was found to contain 0.5% Chrysotile asbestos. Asbestos-containing gold/silver sink undercoat (see Photograph 1 in Appendix B) was observed in the following locations:

- Room 119 (approximately 1 sink);
- Room 122 (approximately 1 sink);
- Room 154/155/156 (approximately 1 sink);
- Room 177 (approximately 1 sink);



ASBESTOS-CONTAINING BUILDING MATERIALS ASSESSMENT REPORT - SASKTEL CENTRE

- Room 206 (approximately 2 sinks); and
- Room 304E (approximately 1 sink).

Red/Brown Duct Mastic

Two (2) samples of red/brown duct mastic were collected during the assessment. Both of the samples collected were found to contain 0.75% to 1.3% Chrysotile asbestos. Asbestos-containing red/brown duct mastic (see Photograph 2 in Appendix B) was observed in the following locations:

- Room 154/155/156 (approximately 15 ft);
- Room 153 (approximately 25 ft);
- Room 130 (approximately 5 ft);
- Room 125 (approximately 30 ft);
- Room 130 (approximately 5 ft);
- Arena Level Ceiling Space Mechanical Room (approximately 600 ft);
- Room 214 (approximately 5 ft);
- Room 210 (approximately 5 ft);
- Room 208 (approximately 5 ft);
- Mezzanine Level Mechanical Room Adjacent S5 (approximately 10 ft);
- Room 324 (approximately 20 ft); and
- Room 301 (approximately 50 ft).

Please note additional asbestos-containing red/brown duct mastic is suspected to be located behind fibreglass insulation and within concealed locations (wall cavities, ceiling spaces and cavities, mechanical shafts, etc.) throughout the Site.

Black Interior Window Caulking

Five (5) samples of black interior window caulking were collected during the assessment. One of the samples collected was found to contain 1.8% Chrysotile asbestos. Asbestos-containing black interior window caulking (see Photograph 3 in Appendix B) was observed on the interior of the exterior windows in the following locations:

- Room 301 (approximately 600 ft);
- Room 304 (approximately 580 ft);
- Room 304A (approximately 200 ft);
- Room 304B (approximately 200 ft);
- Room 304C (approximately 200 ft);
- Room 305 (approximately 225 ft); and
- Room 308 (approximately 260 ft).



The remaining black window caulking located on the exterior of the windows throughout the Site was found to be non-suspect-containing rubber caulking or were found to not contain asbestos through laboratory analysis.

3.1.2 Non Asbestos-Containing Materials

The following materials were sampled during this assessment and were found to not contain asbestos or were observed to be a non-suspect materials:

- Drywall joint compound;
- Blue, white, and dark blue vinyl sheet flooring;
- 1'x1' Ceiling tile with small pinholes and small divots;
- White building caulking;
- Beige mosaic vinyl sheet flooring;
- Tan floor mastic;
- 1'x1' Ceiling tile with very small and small pinholes and short divots;
- Pipe-fitting insulation;
- Plywood joint compound;
- White sink undercoat;
- Blue and white streaked vinyl sheet flooring;
- Yellow floor mastic;
- Grey duct mastic;
- 1'x1' Beige floor tile with black flecks;
- Black interior window caulking (excluding the areas noted in Section 3.1.1);
- White firestop;
- 1'x1' Ceiling tile mastic;
- Boiler exhaust caulking;
- Generator exhaust caulking;
- 2'x4' Ceiling tile with widthwise fissures;
- Grey door window caulking;
- Small beige mosaic vinyl sheet flooring;
- Red firestop;
- 1'x1' Ceiling tile with long fissures;
- Silver duct mastic;



- Concrete scratch coat;
- Beige mosaic with red and turquoise spots vinyl sheet flooring;
- Spray-applied fireproofing;
- Cooler caulking;
- Stucco;
- Black exterior window caulking;
- Grey building caulking;
- White window frame caulking;
- The drain lines throughout the site were not observed to have suspect packing;
- The duct work throughout the site was observed to be uninsulated or insulated with fibreglass insulation;
- The speckled concrete floor coating throughout the Site was found to be constructed of a non-suspect material;
- The duct connector fabric throughout the Site was found to be constructed of a non-suspect material;
- The rubber flooring throughout the site was not sampled as it was visually observed to be constructed of rubber and is not suspected to contain asbestos; and
- The 2'x4' ceiling tiles throughout the Site were found to not contain asbestos from laboratory analysis and date coding.

4.0 EXCLUDED AREAS AND MATERIALS

The following is a list of the areas and/or materials excluded during the assessment.

- Floor levelling compound was not encountered at the time of the assessment. If floor levelling compound is encountered during renovation or demolition activities, sampling should be conducted to evaluate the presence or absence of asbestos.
- The offices located within Room 101 on the Arena Level have gone through renovations and do not match with the floor plans provided. All rooms within Room 101 were assessed, however each individual room number located on the floor plans may not appear within the report or room by room spreadsheet.
- The boilers and associated components were not assessed for asbestos-containing materials during the assessment as sampling could render the equipment non-functional. If the boilers and associated components are scheduled for renovation or demolition activities, additional investigation and sampling of suspect materials may be required.
- Building materials accessible by a ten foot ladder were assessed by Golder during the assessment. Materials located at heights that were inaccessible from a ten foot ladder were not assessed. If materials at heights are to be removed or impacted by future renovation or demolition activities, additional investigation and sampling of suspect materials may be required.



ASBESTOS-CONTAINING BUILDING MATERIALS ASSESSMENT REPORT - SASKTEL CENTRE

- The roof and associated components were not assessed by Golder during the assessment as per Tender 16-0844. If the roof and associated components are to be removed or impacted by future renovation or demolition activities, additional investigation and sampling of suspect materials may be required.
- The duct connector fabric throughout the site was not sampled as causing damage to the fabric could potential release fibres in the air distribution system. Based upon visual observations it is not suspected to contain asbestos, however if the duct connector fabric is scheduled for impact, further sampling may be required.
- The block wall throughout the Site was not destructively investigated for the absence or presence of potential asbestos-containing vermiculite insulation, however various wall penetrations through block were observed throughout the Site and no suspect asbestos-containing vermiculite insulation was observed. Select coring activities may be required in select portions of block wall should they be scheduled for renovation or demolition activities.
- Golder was unable to access Rooms 321, 320, 311, 302, 301B, 218B, 240B, 233, 224, 222, 221D, 103, 166, 167, 168, 169, 170, 171, 186, 187, 188, 189, 190, 191, 140, 137, 134, 133, areas outside of the main walkway of the Gondola Level, and Elevator 2 during the assessment due to locked doors, construction activities, and renovation activities. If work activities are scheduled within these areas, further sampling may be required. If building materials within these areas are to be removed or impacted by future renovation or demolition activities, additional investigation and sampling of suspect materials may be required.
- The Mezzanine Level Mechanical Room Adjacent to S5 and Arena Level Ceiling Space Mechanical Rooms were assessed from the walkways within the area. Additional asbestos-containing building materials may be located within the inaccessible portions of the above areas.

5.0 CONCLUSIONS AND RECOMMENDATIONS

Based on the visual assessment and the laboratory analytical results, the following project specific conclusions and recommendations are provided.

5.1 Asbestos-Containing Materials

Asbestos was positively identified within the gold/silver sink undercoat, red/brown duct mastic, and interior black window caulking within select locations of the Site. Asbestos was not identified in the remaining samples collected and analyzed.

If the building is scheduled for renovations that will impact the identified asbestos-containing materials, it must be removed. If additional suspect asbestos-containing building materials are encountered during renovation activities, additional sampling should be undertaken to evaluate asbestos content.

Removal work should be completed by workers that are adequately trained in the hazards and proper methods of working with asbestos. Throughout the abatement activities, appropriate air monitoring and inspections should be conducted by a competent person to document that contamination is contained and that ACM are disposed of appropriately. Ensure asbestos waste is disposed of in accordance with the requirements of the Government of Saskatchewan.



ASBESTOS-CONTAINING BUILDING MATERIALS ASSESSMENT REPORT - SASKTEL CENTRE

All quantities listed in the report are approximate and are based on the conditions at the time of the assessment. Prior to abatement work it is recommended that a competent person conduct a review of the site to quantify and obtain all measurements of all building materials detailed in this report for cost estimating purposes.

In anticipation of potential abatement, Golder's recommendations for the asbestos-containing materials identified during the assessment are outlined below.

Gold/Silver Sink Undercoat

If scheduled for impact, asbestos-containing gold/silver sink undercoat should be abated following low-risk abatement work procedures as outlined in the *Saskatchewan Asbestos Abatement Manual* (2017). Alternatively, as the gold/silver sink undercoat was observed in good condition, and with a priority rating of 5 (please see the room by room spreadsheet provided in Appendix C for a description of the priority ratings), it can be managed in place if not scheduled for impact.

Red/Brown Duct Mastic

If scheduled for impact, asbestos-containing red/brown duct mastic should be abated following low-risk abatement work procedures as outlined in the *Saskatchewan Asbestos Abatement Manual* (2017). Alternatively, as the red/brown duct mastic was observed in good condition, and with a priority rating of 5 (please see the room by room spreadsheet provided in Appendix C for a description of the priority ratings), it can be managed in place if not scheduled for impact.

Black Interior Window Caulking

If scheduled for impact, asbestos-containing black interior window caulking should be abated following low-risk abatement work procedures as outlined in the *Saskatchewan Asbestos Abatement Manual* (2017). Alternatively, as the black interior window caulking was observed in good condition, and with a priority rating of 5 (please see the room by room spreadsheet provided in Appendix C for a description of the priority ratings), it can be managed in place if not scheduled for impact.

6.0 SURVEY LIMITATIONS

This report is based on data and information collected by Golder during the assessment conducted on May 29, 30, and 31, 2017 and is based solely on site conditions encountered at the time of the assessment. Any use of this document or the findings, conclusions or recommendations provided in this report by any person other than the City of Saskatoon is at the sole risk of such user.

The conclusions and recommendations contained in this survey report are based upon professional opinions with regard to the subject matter. These opinions are in accordance with currently accepted environmental assessment standards and practices applicable to these locations and are subject to the following inherent limitations:

The data and findings presented in this report are valid as of the dates of the investigations. The passage of time, manifestation of latent conditions or occurrence of future events may warrant further exploration at the properties, analysis of the data, and re-evaluation of the findings, observations, and conclusions expressed in this report. No assurance is made regarding changes in conditions or practices subsequent to the time of the investigation. It was beyond the scope of this assessment to conduct a risk assessment and the potential health risks that may be associated with asbestos exposure for building occupants.



ASBESTOS-CONTAINING BUILDING MATERIALS ASSESSMENT REPORT - SASKTEL CENTRE

The data reported and the findings, observations and conclusions expressed in this report are limited by the Scope of Work. The Scope of Work was defined by Tender 16-0844 and the initial site walkthrough with the Client, the time and budgetary constraints imposed by the Client, and availability of access to the property.

Because of the limitations stated above, the findings, observations and conclusions expressed by Golder in this report are not, and must not be, considered an opinion concerning compliance of any past or present owner or operator of the site with any federal, provincial or local laws or regulations.

No warranty or guarantee, whether expressed or implied, is made with respect to the data or the reported findings, observations, and conclusions, which are based solely upon site conditions in existence at the time of investigation.

Golder's assessment reports present professional opinions and findings of a scientific and technical nature. While attempts were made to relate the data and findings to applicable environmental laws and regulations, the report shall not be construed to offer legal opinion or representations as to the requirements of, nor compliance with, environmental laws, rules, regulations or policies of federal, provincial, or local governmental agencies. Any use of the survey report constitutes acceptance of the limits of Golder's liability.

Golder's liability extends only to its client and not to other parties who may obtain this survey report. Issues raised by the report must be reviewed by appropriate legal counsel.

7.0 CLOSURE

We trust the information presented in this report meets your requirements. If you have any questions please contact Kody Henderson at (780) 483-3499 or email at kody_henderson@golder.com. Thank you for the opportunity to be of service. We look forward to working with you again in the future.



ASBESTOS-CONTAINING BUILDING MATERIALS ASSESSMENT REPORT - SASKTEL CENTRE

Report Signature Page

GOLDER ASSOCIATES LTD.

Prepared by:

Kody Henderson, Dipl. Env. Sci., CRSP
OHS Project Manager

Reviewed by:

Andrew Grant, B.Sc., P.Eng., EP, CRSP
Associate, OHS Project Director

KH/AG/ba

Golder, Golder Associates and the GA globe design are trademarks of Golder Associates Corporation.

\\golder\galleddmonton\active\2016\3 proj\1667963 cityofsaskatoon_asbsurveys_saskatoon\07 reports\05 - sasktel centre\city of saskatoon - sasktel centre - asbestos building material assessment report.docx



APPENDIX A

Laboratory Certificate of Analysis Report

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258488
Client No.: A-001

Percent Asbestos:
None Detected

Description: White Joint Compound
Facility:

Percent Non-Asbestos Fibrous Material:
None Detected

Location: Room 118

Percent Non-Fibrous Material:
100

Lab No.: 6258489
Client No.: A-002

Percent Asbestos:
None Detected

Description: Off White Joint Compound
Facility:

Percent Non-Asbestos Fibrous Material:
None Detected

Location: Room 119

Percent Non-Fibrous Material:
100

Lab No.: 6258489(L2)
Client No.: A-002

Percent Asbestos:
None Detected

Description: Tan Mastic
Facility:

Percent Non-Asbestos Fibrous Material:
None Detected

Location: Room 119

Percent Non-Fibrous Material:
100

Lab No.: 6258490
Client No.: A-003

Percent Asbestos:
None Detected

Description: White/Light Grey/Blue Vinyl
Sheet Flooring
Facility:
Percent Non-Asbestos Fibrous Material:
10 Cellulose
2 Fibrous Glass

Location: Room 119

Percent Non-Fibrous Material:
88

Lab No.: 6258491
Client No.: A-004

Percent Asbestos:
None Detected

Description: White/Tan Ceiling Tile
Facility:
Percent Non-Asbestos Fibrous Material:
65 Cellulose
5 Mineral Wool

Location: Room 119

Percent Non-Fibrous Material:
30

Lab No.: 6258492
Client No.: A-005

Percent Asbestos:
PC 0.5 Chrysotile

Description: Gold/Black Mastic
Facility:
Percent Non-Asbestos Fibrous Material:
2 Cellulose

Location: Room 119

Percent Non-Fibrous Material:
97.5

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 6/7/2017

Date Analyzed: 06/14/2017

Signature:

Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258493
Client No.: A-006

Description: White Caulk
Facility:

Location: Room 114

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 6258494
Client No.: A-007

Description: White/Light Grey Vinyl Sheet
Flooring
Facility:
Percent Non-Asbestos Fibrous Material:
5 Cellulose
5 Synthetic
2 Fibrous Glass

Location: Room 122

Percent Asbestos:
None Detected

Percent Non-Fibrous Material:
88

Lab No.: 6258494(L2)
Client No.: A-007

Description: Tan Mastic
Facility:

Location: Room 122

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 6258495
Client No.: A-008

Description: White/Tan Ceiling Tile
Facility:
Percent Non-Asbestos Fibrous Material:
50 Cellulose
20 Mineral Wool

Location: Room 122

Percent Asbestos:
None Detected

Percent Non-Fibrous Material:
30

Lab No.: 6258496
Client No.: A-009

Description: Light Tan Joint Compound
Facility:

Location: Room 122

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 6/7/2017

Date Analyzed: 06/14/2017

Signature:

Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258497	Description: Light Grey Insulation	Location: Room 125
Client No.: A-010	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	20 Mineral Wool	80

Lab No.: 6258498	Description: White/Tan Ceiling Tile	Location: Room 131
Client No.: A-011	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	50 Cellulose 20 Mineral Wool	30


Lab No.: 6258499	Description: Grey Insulation	Location: Room 132
Client No.: A-012	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	25 Mineral Wool	75


Lab No.: 6258500	Description: White Joint Compound	Location: Room 136
Client No.: A-013	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100

Lab No.: 6258501	Description: White Joint Compound	Location: Room 138
Client No.: A-014	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100

Lab No.: 6258502	Description: White/Light Tan Ceiling Tile	Location: Room 141
Client No.: A-015	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	60 Cellulose 10 Mineral Wool	30

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258503	Description: White/Tan Ceiling Tile	Location: Room 141
Client No.: A-016	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	50 Cellulose 20 Mineral Wool	30

Lab No.: 6258504	Description: Grey Insulation	Location: Room 194
Client No.: A-017	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	2 Synthetic	98


Lab No.: 6258505	Description: Red/Brown Mastic	Location: Room 155
Client No.: A-018	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>PC 0.75 Chrysotile</i>	None Detected	99.25


Lab No.: 6258506	Description: White/Blue Vinyl Sheet Flooring	Location: Room 101.8
Client No.: A-019	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100

Lab No.: 6258506(L2)	Description: Yellow Mastic	Location: Room 101.8
Client No.: A-019	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100

Lab No.: 6258507	Description: White Joint Compound	Location: Room 101.8
Client No.: A-020	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572


PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258508 Client No.: A-021 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan/Light Pink Sheetrock Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 5 Cellulose	Location: Room 101.11 <u>Percent Non-Fibrous Material:</u> 95
Lab No.: 6258508(L2) Client No.: A-021 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: White Joint Compound Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 101.11 <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258508(L3) Client No.: A-021 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: White Texture/Plaster Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 101.11 <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258509 Client No.: A-022 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: White Joint Compound Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 102.4 <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258510 Client No.: A-023 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: White Joint Compound Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 101.2 <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258510(L2) Client No.: A-023 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan Mastic Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 101.2 <u>Percent Non-Fibrous Material:</u> 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017

Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963


Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY


Lab No.: 6258511 Client No.: A-024	Description: Grey Mastic Facility:	Location: Room 101.2
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258512 Client No.: A-025	Description: Beige Floor Tile Facility:	Location: Room 113
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258513 Client No.: A-026	Description: Off White/Yellow/Light Grey Insulation Facility:	Location: Room 111
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 5 Cellulose 70 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 25
Lab No.: 6258514 Client No.: A-027	Description: Black Caulk Facility:	Location: Room 112
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 2 Cellulose	<u>Percent Non-Fibrous Material:</u> 98
Lab No.: 6258515 Client No.: A-028	Description: White Caulk Facility:	Location: Room 107
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258516 Client No.: A-029	Description: White/Tan Ceiling Tile Facility:	Location: Room 106
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 40 Cellulose 30 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017

Signature: 
Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258517	Description: Tan Mastic	Location: Room 106
Client No.: A-030	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258518	Description: Light Grey Insulation	Location: Room 149
Client No.: A-031	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 20 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 80


Lab No.: 6258519	Description: Off White/Silver Wrap	Location: Room 149
Client No.: A-032	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 95 Cellulose	<u>Percent Non-Fibrous Material:</u> 5


Lab No.: 6258519(L2)	Description: Yellow/Brown Insulation	Location: Room 149
Client No.: A-032	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 100 Mineral Wool	<u>Percent Non-Fibrous Material:</u> None Detected

Lab No.: 6258520	Description: Light Grey Insulation	Location: Room 149
Client No.: A-033	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 20 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 80

Lab No.: 6258521	Description: Clear Caulk	Location: Room 149
Client No.: A-034	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3


Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963


Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258522 Client No.: A-035	Description: Grey/Yellow Insulation Facility:	Location: Room 149
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 80 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 20
Lab No.: 6258522(L2) Client No.: A-035	Description: White Mastic Facility:	Location: Room 149
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258523 Client No.: A-036	Description: Silver/Dark Grey Caulk Facility:	Location: Room 151
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258524 Client No.: A-037	Description: White/Tan Ceiling Tile Facility:	Location: Room 215
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 50 Cellulose 20 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30
Lab No.: 6258525 Client No.: A-038	Description: Grey Insulation Facility:	Location: Room 214
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 20 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 80
Lab No.: 6258526 Client No.: A-039	Description: White/Tan Ceiling Tile Facility:	Location: Room 210
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258527	Description: White/Tan Ceiling Tile	Location: Room 210
Client No.: A-040	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	70 Cellulose Trace Mineral Wool	30

Lab No.: 6258528	Description: White Joint Compound	Location: Room 210
Client No.: A-041	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100


Lab No.: 6258529	Description: Grey Caulk	Location: Room 208
Client No.: A-042	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100


Lab No.: 6258530	Description: White/Tan Ceiling Tile	Location: Room 204B
Client No.: A-043	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	70 Cellulose Trace Mineral Wool	30

Lab No.: 6258531	Description: White Joint Compound	Location: Room 204B
Client No.: A-044	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	None Detected	100

Lab No.: 6258532	Description: White/Tan Ceiling Tile	Location: Room 207B
Client No.: A-045	Facility:	
<u>Percent Asbestos:</u>	<u>Percent Non-Asbestos Fibrous Material:</u>	<u>Percent Non-Fibrous Material:</u>
<i>None Detected</i>	65 Cellulose 5 Mineral Wool	30

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258533
Client No.: A-046

Percent Asbestos:
None Detected

Description: Tan/Off White Sheetrock
Facility:

Percent Non-Asbestos Fibrous Material:
Trace Fibrous Glass
5 Cellulose

Location: Room 207B

Percent Non-Fibrous Material:
95

Lab No.: 6258534
Client No.: A-047

Percent Asbestos:
None Detected

Description: Beige/Pink Vinyl Sheet Flooring
Facility:

Percent Non-Asbestos Fibrous Material:
10 Cellulose
10 Synthetic
2 Fibrous Glass

Location: Room 207B

Percent Non-Fibrous Material:
78

Lab No.: 6258535
Client No.: A-048

Percent Asbestos:
None Detected

Description: White Joint Compound
Facility:

Percent Non-Asbestos Fibrous Material:
None Detected

Location: Room 245

Percent Non-Fibrous Material:
100

Lab No.: 6258536
Client No.: A-049

Percent Asbestos:
None Detected

Description: Grey Insulation
Facility:

Percent Non-Asbestos Fibrous Material:
20 Mineral Wool

Location: Room 243

Percent Non-Fibrous Material:
80

Lab No.: 6258537
Client No.: A-050

Percent Asbestos:
None Detected

Description: White/Tan Ceiling Tile
Facility:

Percent Non-Asbestos Fibrous Material:
50 Cellulose
20 Mineral Wool

Location: Room 244

Percent Non-Fibrous Material:
30

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 6/7/2017

Date Analyzed: 06/14/2017

Signature:

Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258538
Client No.: A-051

Description: White Joint Compound
Facility:

Location: Room 241

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 6258539
Client No.: A-052

Description: Black Caulk
Facility:

Location: Lobby Adjacent to Room 237B

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 6258540
Client No.: A-053

Description: Tan/White Sheetrock
Facility:

Location: Room 236B

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
5 Cellulose

Percent Non-Fibrous Material:
95

Lab No.: 6258540(L2)
Client No.: A-053

Description: White Joint Compound
Facility:

Location: Room 236B

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 6258541
Client No.: A-054

Description: White/Tan Ceiling Tile
Facility:

Location: Room 225

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
50 Cellulose
20 Mineral Wool

Percent Non-Fibrous Material:
30

Lab No.: 6258542
Client No.: A-055

Description: White Joint Compound
Facility:

Location: Room 220B

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 6/7/2017

Date Analyzed: 06/14/2017

Signature:

Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258543	Description: Light Grey Insulation	Location: Room 220B
Client No.: A-056	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 20 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 80

Lab No.: 6258544	Description: White Joint Compound	Location: Room 219A
Client No.: A-057	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100


Lab No.: 6258545	Description: Tan/Off White Sheetrock	Location: Room CS276
Client No.: A-058	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 5 Cellulose	<u>Percent Non-Fibrous Material:</u> 95


Lab No.: 6258545(L2)	Description: White Joint Compound	Location: Room CS276
Client No.: A-058	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258546	Description: White Joint Compound	Location: Room G-3
Client No.: A-059	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258547	Description: White Joint Compound	Location: Room CS277
Client No.: A-060	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258548 Client No.: A-061	Description: White Joint Compound Facility:	Location: Room G-7
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258549 Client No.: A-062	Description: Light Brown Caulk Facility:	Location: Main Level CS Walkway
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258550 Client No.: A-063	Description: White/Tan Ceiling Tile Facility:	Location: Room 247
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30
Lab No.: 6258551 Client No.: A-064	Description: White/Tan Ceiling Tile Facility:	Location: Room 247
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30
Lab No.: 6258552 Client No.: A-065	Description: White/Tan Ceiling Tile Facility:	Location: Room 247
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30
Lab No.: 6258553 Client No.: A-066	Description: Grey Mastic Facility:	Location: Room 409
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 2 Cellulose	<u>Percent Non-Fibrous Material:</u> 98

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 6/7/2017

Date Analyzed: 06/14/2017

Signature:

Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258554	Description: Silver/Yellow Paint/Caulk	Location: Room 409
Client No.: A-067	Facility:	
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Different Material analyzed than listed on the sample log.


Lab No.: 6258555	Description: White/Tan Ceiling Tile	Location: Room 401
Client No.: A-068	Facility:	
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30


Lab No.: 6258556	Description: White/Tan Ceiling Tile	Location: Room 401
Client No.: A-069	Facility:	
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30

Lab No.: 6258557	Description: White/Tan Ceiling Tile	Location: Room 405
Client No.: A-070	Facility:	
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 65 Cellulose 5 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30

Lab No.: 6258558	Description: White/Tan Ceiling Tile	Location: Room 407
Client No.: A-071	Facility:	
<u>Percent Asbestos:</u> <i>None Detected</i>	<u>Percent Non-Asbestos Fibrous Material:</u> 60 Cellulose 10 Mineral Wool	<u>Percent Non-Fibrous Material:</u> 30

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963


Client: GOL572


PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258559 Client No.: A-072	Description: Grey Concrete Facility:	Location: Room 407
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258560 Client No.: A-073	Description: Grey Concrete Facility:	Location: Stairwell 1
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258561 Client No.: A-074	Description: Grey Concrete Facility:	Location: Stairwell 1
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258562 Client No.: A-075	Description: Grey Concrete Facility:	Location: Stairwell 1
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258563 Client No.: A-076	Description: Grey Concrete Facility:	Location: Stairwell 1
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258564 Client No.: A-077	Description: White Joint Compound Facility:	Location: Stairwell 1
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017

Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3


Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963


Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258565 Client No.: A-078	Description: Grey Concrete Facility:	Location: Stairwell 3
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258566 Client No.: A-079	Description: Grey Concrete Facility:	Location: Stairwell 3
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258567 Client No.: A-080	Description: Grey Concrete Facility:	Location: Stairwell 3
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258568 Client No.: A-081	Description: White Joint Compound Facility:	Location: Room 3.01.03
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258569 Client No.: A-082	Description: Tan/White Sheetrock Facility:	Location: Room 312
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose	<u>Percent Non-Fibrous Material:</u> 90
Lab No.: 6258570 Client No.: A-083	Description: Dark Red Mastic Facility:	Location: Mechanical Room Adjacent to Stairwell 5
<u>Percent Asbestos:</u> PC 1.3 Chrysotile	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 98.7

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3


Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963


Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258571 Client No.: A-084	Description: Beige/Light Grey Vinyl Sheet Flooring Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose 10 Synthetic Trace Fibrous Glass	Location: Room 318 <u>Percent Non-Fibrous Material:</u> 80
Lab No.: 6258572 Client No.: A-085	Description: White Joint Compound Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Storage Room Adjacent to Room 320 <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258573 Client No.: A-086	Description: White Joint Compound Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 323 <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258574 Client No.: A-087	Description: White Joint Compound Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 301D <u>Percent Non-Fibrous Material:</u> 100
Lab No.: 6258575 Client No.: A-088	Description: Black Caulk Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 2 Cellulose	Location: Room 301 <u>Percent Non-Fibrous Material:</u> 98
Lab No.: 6258576 Client No.: A-089	Description: Black Caulk Facility: <u>Percent Non-Asbestos Fibrous Material:</u> None Detected	Location: Room 301 <u>Percent Non-Fibrous Material:</u> 98.2

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963


Client: GOL572


PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258577 Client No.: A-090 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Black Caulk Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 2 Cellulose	Location: Room 3.13.1 <u>Percent Non-Fibrous Material:</u> 98
Lab No.: 6258578 Client No.: A-091 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan Insulation Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose	Location: Third Floor Concourse <u>Percent Non-Fibrous Material:</u> 90
Lab No.: 6258579 Client No.: A-092 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan Insulation Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose	Location: Third Floor Concourse <u>Percent Non-Fibrous Material:</u> 90
Lab No.: 6258580 Client No.: A-093 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan Insulation Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose	Location: Third Floor Concourse <u>Percent Non-Fibrous Material:</u> 90
Lab No.: 6258581 Client No.: A-094 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan Insulation Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose	Location: Third Floor Concourse <u>Percent Non-Fibrous Material:</u> 90
Lab No.: 6258582 Client No.: A-095 <u>Percent Asbestos:</u> <i>None Detected</i>	Description: Tan Insulation Facility: <u>Percent Non-Asbestos Fibrous Material:</u> 10 Cellulose	Location: Third Floor Concourse <u>Percent Non-Fibrous Material:</u> 90

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017

Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258583	Description: White Joint Compound	Location: Third Floor Concourse
Client No.: A-096	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258584	Description: White Joint Compound	Location: Third Floor Concourse
Client No.: A-097	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100


Lab No.: 6258585	Description: Clear/White Caulk	Location: Room 328B
Client No.: A-098	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100


Lab No.: 6258586	Description: Grey Stucco	Location: Exterior
Client No.: A-099	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258587	Description: Grey Stucco	Location: Exterior
Client No.: A-100	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258588	Description: Grey Stucco	Location: Exterior
Client No.: A-101	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258589	Description: Grey Stucco	Location: Exterior
Client No.: A-102	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258590	Description: Grey Stucco	Location: Exterior
Client No.: A-103	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100


Lab No.: 6258591	Description: Grey Stucco	Location: Exterior
Client No.: A-104	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100


Lab No.: 6258592	Description: Grey Stucco	Location: Exterior
Client No.: A-105	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258593	Description: Black Caulk	Location: Exterior
Client No.: A-106	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Lab No.: 6258594	Description: Black Caulk	Location: Exterior
Client No.: A-107	Facility:	
<u>Percent Asbestos:</u> None Detected	<u>Percent Non-Asbestos Fibrous Material:</u> None Detected	<u>Percent Non-Fibrous Material:</u> 100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.

Date Received: 6/7/2017
Date Analyzed: 06/14/2017
Signature: 
Analyst: Muhammad Mirza

Approved By: 
Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 6258595
Client No.: A-108

Percent Asbestos:
None Detected

Description: Light Grey Caulk
Facility:

Percent Non-Asbestos Fibrous Material:
None Detected

Location: Exterior

Percent Non-Fibrous Material:
100

Lab No.: 6258596
Client No.: A-109

Percent Asbestos:
None Detected

Description: Light Grey Caulk
Facility:

Percent Non-Asbestos Fibrous Material:
None Detected

Location: Exterior

Percent Non-Fibrous Material:
100

Analytical Method -US EPA 600, R93-116. Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 6/7/2017

Date Analyzed: 06/14/2017

Signature:

Analyst: Muhammad Mirza

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

Appendix to Analytical Report

Customer Contact:

Analysis: US EPA 600, R93-116

This appendix seeks to promote greater understanding of any observations, exceptions, special instructions, or circumstances that the laboratory needs to communicate to the client concerning the above samples. The information below is used to help promote your ability to make the most informed decisions for you and your customers. Please note the following points of contact for any questions you may have.

iATL Customer Service: customerservice@iatl.com

iATL Office Manager: cdavis@iatl.com

iATL Account Representative: Pete Lesniak

Sample Login Notes: See Batch Sheet Attached

Sample Matrix: Bulk Building Materials

Exceptions Noted: See Following Pages

General Terms, Warrants, Limits, Qualifiers:

General information about iATL capabilities and client/laboratory relationships and responsibilities are spelled out in iATL policies that are listed at www.iATL.com and in our Quality Assurance Manual per ISO 17025 standard requirements. The information therein is a representation of iATL definitions and policies for turnaround times, sample submittal, collection media, blank definitions, quantification issues and limit of detection, analytical methods and procedures, sub-contracting policies, results reporting options, fees, terms, and discounts, confidentiality, sample archival and disposal, and data interpretation.

iATL warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted. iATL disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. iATL accepts no legal responsibility for the purpose for which the client uses test results. Any analytical work performed must be governed by our Standard Terms and Conditions. Prices, methods and detection limits may be changed without notification. Please contact your Customer Service Representative for the most current information.

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA LAP LLC, or any agency of local, state or province governments nor of any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Information Pertinent to this Report:

Analysis by US EPA 600 93-116: Determination of Asbestos in Bulk Building Materials by Polarized Light Microscopy (PLM).

Certifications:

- NIST-NVLAP No. 101165-0
- NY-DOH No. 11021
- AIHA-LAP, LLC No. 100188

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analytical Methodology Alternatives: Your initial request for analysis may not have accounted for recent advances in regulatory requirements or advances in technology that are routinely used in similar situations for other qualified projects. You may have the option to explore additional analysis for further information. Below are a few options, listed as the matrix followed by the appropriate methodology. Also included are links to more information on our website.

Bulk Building Materials that are Non-Friable Organically Bound (NOB) by Gravimetric Reduction techniques employing PLM and TEM: ELAP 198.6 (PLM-NOB), ELAP 198.4 (TEM-NOB)

Loose Fill Vermiculite Insulation, Attic Insulation, Zonolite (copyright), etc.: US EPA 600 R-4/004 (multi-tiered analytical process)
Sprayed On Insulation/Fireproofing with Vermiculite (SOF-V): ELAP 198.8 (PLM-SOF-V)>

Soil, sludge, sediment, aggregate, and like materials analyzed for asbestos or other elongated mineral particles (ex. erionite, etc.): ASTM D7521, CARB 435, and other options available

CERTIFICATE OF ANALYSIS

Client: Golder Associates Ltd
16820 107 Ave
Edmonton AB T5P 4C3

Report Date: 6/14/2017
Report No.: 538139 - PLM
Project: Asbestos Surveys – City of Saskatoon
Project No.: 1667963

Client: GOL572

Asbestos in Surface Dust according to one of ASTM's Methods (very dependent on sampling collection technique – by TEM): ASTM D 5755, D5756, or D6480

Various other asbestos matrices (air, water, etc.) and analytical methods are available.

Disclaimers / Qualifiers:

There may be some samples in this project that have a "NOTE:" associated with a sample result. We use added disclaimers or qualifiers to inform the client about something that requires further explanation. Here is a list with highlighted disclaimers that may be pertinent to this project. For a full explanation of these and other disclaimers, please inquire at customerservice@iatl.com.

- 1) Note: No mastic provided for analysis.
- 2) Note: Insufficient mastic provided for analysis.
- 3) Note: Insufficient material provided for analysis.
- 4) Note: Insufficient sample provided for QC reanalysis.
- 5) Note: Different material than indicated on Sample Log / Description.
- 6) Note: Sample not submitted.
- 7) Note: Attached to asbestos containing material.
- 8) Note: Received wet.
- 9) Note: Possible surface contamination.
- 10) Note: Not building material. 1% threshold may not apply.
- 11) Note: Recommend TEM-NOB analysis as per EPA recommendations.
- 12) Note: Asbestos detected but not quantifiable.
- 13) Note: Multiple identical samples submitted, only one analyzed.
- 14) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.080%.
- 15) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.125%.

Recommendations for Vermiculite Analysis:

Several analytical protocols exist for the analysis of asbestos in vermiculite. These analytical approaches vary depending upon the nature of the vermiculite mineral being tested (e.g. un-processed gangue, homogeneous exfoliated books of mica, or mixed mineral composites). Please contact your client representative for pricing and turnaround time options available.

iATL recommends initial testing using the EPA 600/R-93/116 method. This method is specifically designed for the analysis of asbestos in bulk building materials. It provides an acceptable starting point for primary screening of vermiculite for possible asbestos.

Results from this testing may be inconclusive. EPA suggests proceeding to a multi-tiered analysis involving wet separation techniques in conjunction with PLM and TEM gravimetric analysis (EPA 600/R-04/004).

Further information on this method and other vermiculite and asbestos issues can be found at the following: Agency for Toxic Substances and Disease Registry (ATSDR) www.atsdr.cdc.gov, United States Geological Survey (USGS) www.minerals.usgs.gov/minerals/, US EPA www.epa.gov/asbestos. The USEPA also has an informative brochure "Current Best Practices for Vermiculite Attic Insulation" EPA 747F03001 May 2003, that may assist the health and remediation professional.

The following is a summary of the analytical process outlines in the EPA 600/R-04/004 Method:

- 1) **Analytical Step/Method:** Initial Screening by PLM, EPA 600R-93/116
Requirements/Comments: Minimum of 0.1 g of sample. ~0.25% LOQ for most samples.
- 2) **Analytical Step/Method:** Wet Separation by PLM Gravimetric Technique, EPA R-04/004
Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Sinks" only.
- 3) **Analytical Step/Method:** Wet Separation by PLM Gravimetric Technique, EPA R-04/004
Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Floats" only.
- 4) **Analytical Step/Method:** Wet Separation by TEM Gravimetric Technique, EPA R-04/004
Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Sinks" only.
- 5) **Analytical Step/Method:** Wet Separation by TEM Gravimetric Technique, EPA R-04/004
Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Suspension" only.

LOQ, Limit of Quantitation estimates for mass and volume analyses.

*With advance notice and confirmation by the laboratory.

**Approximately 1 Liter of sample in double-bagged container (~9x6 inch bag of sample).



APPENDIX B

Site Photographs



APPENDIX B

Site Photographs



Photograph 1: Asbestos-Containing Gold/Silver Sink Undercoat.




Photograph 2: Asbestos-Containing Red/Brown Duct Mastic.



APPENDIX B

Site Photographs



Photograph 3: Asbestos-Containing Black Interior Window Caulking.

\\golder\galledmonton\active\2016\3 proj\1667963 cityofsaskatoon_asbsurveys_saskatoon\07 reports\05 - sasktel centre\appendix b - site photographs.docx



APPENDIX C

Room by Room Spreadsheet

Appendix C
Sasktel Centre
ACM Inventory

Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	All	Throughout	All	Doors	Regular Door	Non Suspect Door	High	No	No	No	Good	Non-suspect doors were observed throughout the Site. White building caulking is located sporadically on walls throughout the Site.																
Included	All	Throughout	All	Walls	Caulking	White Building Caulking	High	No	Yes	No	Good																	
Included	A	101.1	Dressing Room	Walls	Block Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.1	Dressing Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.1	Dressing Room	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	101.1	Dressing Room	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	101.1	Dressing Room	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.2	Dressing Room	Walls	Walls	Block Walls	High	No	No	No	Good		Bulk	A-023	30-May-17													
Included	A	101.2	Dressing Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.2	Dressing Room	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	101.2	Dressing Room	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.2	Dressing Room	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	A	101.2	Halfway	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.2	Halfway	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.2	Halfway	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	101.2	Halfway	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.2	Halfway	Mechanical	Duct Work	Grey Duct Mastic	Low	No	Yes	No	Good		Bulk	A-024	30-May-17													
Included	A	101.3	Fitness Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.3	Fitness Room	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	101.3	Fitness Room	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.6	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.6	Office	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	A	101.6	Office	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.7	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.7	Office	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.7	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	101.7	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.8	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.8	Office	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.8	Office	Floor	Floor	Blue and White Streaked Vinyl Sheet Flooring	High	No	Yes	No	Good		Bulk	A-019	30-May-17													
Included	A	101.8	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.8	Office	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	A	101.9	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-020	30-May-17													
Included	A	101.9	Office	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.9	Office	Floor	Floor	New Vinyl Sheet Flooring	High	No	No	No	Good																	
Included	A	101.9	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.9	Office	Windows	Windows	Black Interior Window Caulking	High	No	Yes	No	Good																	
Included	A	101.10	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.10	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	101.10	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.11	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-021	30-May-17													
Included	A	101.11	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	101.11	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.21 and 101.22	Shower/Storage Area	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.21 and 101.22	Shower/Storage Area	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.21 and 101.22	Shower/Storage Area	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	101.21 and 101.22	Shower/Storage Area	Ceiling	Ceiling	Ceiling Tile	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.23	Laundry Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.23	Laundry Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.23	Laundry Room	Floor	Floor	Blue and White Streaked Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	101.23	Laundry Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.24 and 101.25	Medical and Trainer Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.24 and 101.25	Medical and Trainer Office	Floor	Floor	Carpet	High	No	Yes	No	Good																	
Included	A	101.24 and 101.25	Medical and Trainer Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	101.24 and 101.25	Medical and Trainer Office	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	A	101.26	Skate and Equipment Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	101.26	Skate and Equipment Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	101.26	Skate and Equipment Room	Floor	Floor	Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	101.26	Skate and Equipment Room	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	102.1	Sticks	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	102.1	Sticks	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	102.1	Sticks	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	102.1	Sticks	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	102.4	Halfway	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-022	30-May-17													
Included	A	102.4	Halfway	Floor	Floor	New Vinyl Sheet Flooring	High	No	No	No	Good																	
Included	A	102.4	Halfway	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	106	Event Office	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	106	Event Office	Floor	Floor	New Vinyl Sheet Flooring	High	No	No	No	Good																	
Included	A	106	Event Office	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-029	30-May-17													
Included	A	106	Event Office	Ceiling	Ceiling	Ceiling Tile Mastic	High	No	Yes	No	Good		Bulk	A-030	30-May-17													
Included	A	107	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	107	Electrical Room	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	107	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	107	Electrical Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	107	Electrical Room	Mechanical	Firestop	White Firestop	High	No	Yes	No	Good		Bulk	A-028	30-May-17													
Included	A	107	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually	Low	Inspect and sample if scheduled for removal.				
Included	A	110	Loading Dock	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	110	Loading Dock	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	110	Loading Dock	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	110	Loading Dock	Ceiling	Ceiling	Concrete	High	No	No																			

Appendix C
Sasktel Centre
ACM Inventory

Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	A	113	Security Trailer	Ceiling	Ceiling	Pre-Fabricated Panels	High	No	Yes	No	Good																	
Included	A	114	Finishing Kitchen	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	114	Finishing Kitchen	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	114	Finishing Kitchen	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	114	Finishing Kitchen	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	114	Finishing Kitchen	Walls	Caulking	White Building Caulking	High	No	Yes	No	Good		Bulk	A-006	30-May-17													
Included	A	114	Finishing Kitchen	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	115	Catering Kitchen	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	115	Catering Kitchen	Walls	Walls	Concrete	High	No	Yes	No	Good																	
Included	A	115	Catering Kitchen	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	A	115	Catering Kitchen	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	115	Catering Kitchen	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	117	Concession	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	117	Concession	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	A	117	Concession	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	118	Concession Storage	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	118	Concession Storage	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	A	118	Concession Storage	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-001	30-May-17													
Included	A	119	Staff Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	119	Staff Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-002	30-May-17													
Included	A	119	Staff Room	Floor	Floor	Blue, White, and Dark Blue Speckled Vinyl Sheet Flooring	High	No	Yes	No	Good		Bulk	A-003	30-May-17													
Included	A	119	Staff Room	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-004	30-May-17													
Included	A	119	Staff Room	Plumbing	Sink	Gold Sink Undercoat	High	Yes	Yes	Yes	Good		Bulk	A-005	30-May-17	Chrysotile	Sink Undercoat	0.50%	No	No	No	Annually	5	Moderate	Manage in place	1 Sink	Photograph 1	Door Jamb
Included	A	120	Washroom	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	120	Washroom	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	120	Washroom	Floor	Floor	Blue, White, and Dark Blue Speckled Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	120	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	121	Locker Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	121	Locker Room	Walls	Walls	Ceramic Tile	High	No	No	No	Good																	
Included	A	121	Locker Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	121	Locker Room	Floor	Floor	Blue, White, and Dark Blue Speckled Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	121	Locker Room	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	A	122	Staff Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	122	Staff Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-009	30-May-17													
Included	A	122	Staff Room	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring	High	No	Yes	No	Good		Bulk	A-007	30-May-17													
Included	A	122	Staff Room	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-008	30-May-17													
Included	A	122	Staff Room	Plumbing	Sink	Gold Sink Undercoat	High	Yes	Yes	Yes	Good		Bulk	VS A-005	30-May-17	Chrysotile	Sink Undercoat	0.50%	No	No	No	Annually	5	Moderate	Manage in place	1 Sink	Photograph 1	Door Jamb
Included	A	123	Staff Area	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	123	Staff Area	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	123	Staff Area	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	123	Staff Area	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	A	123	Staff Area	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	125	Event Staff Area	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	125	Event Staff Area	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	125	Event Staff Area	Floor	Floor	Blue, White, and Dark Blue Speckled Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	125	Event Staff Area	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	125	Event Staff Area	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	125	Event Staff Area	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-010	30-May-17													
Included	A	125	Event Staff Area	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	30 ft	Photograph 2	Door Jamb
Included	A	128	Loading Dock	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	128	Loading Dock	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	128	Loading Dock	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	128	Loading Dock	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	128	Loading Dock	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	A	130	Loading Dock	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	130	Loading Dock	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	130	Loading Dock	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	130	Loading Dock	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	130	Loading Dock	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	A	130	Loading Dock	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	5 ft	Photograph 2	Door Jamb
Included	A	131	Washroom	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	131	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	131	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	A	131	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-011	30-May-17													
Included	A	132	Mechanical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	132	Mechanical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	132	Mechanical Room	Ceiling	Ceiling	Concrete	High	No	Yes	No	Good																	
Included	A	132	Mechanical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-012	30-May-17													
Included	A	135	Office	Walls	Walls	Drywall Joint Compound	High	No	No	No	Good																	
Included	A	135	Office	Floor	Floor	Carpet	High	No	Yes	No	Good																	
Included	A	135	Office	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	136	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-013	30-May-17													
Included	A	136	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	136	Office	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	A	136	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	138	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	138	Office	Walls	Walls	Plywood with Compound	High	No	Yes	No	Good		Bulk	A-014	30-May-17													
Included	A	138	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	138	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures and 2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	139	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	

Appendix C
Sasktel Centre
ACM Inventory

Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	A	147	Shop	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	148	Refrigeration Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	148	Refrigeration Room	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	148	Refrigeration Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	148	Refrigeration Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	148	Refrigeration Room	Mechanical	Caulking	Grey Exhaust Caulking	High	No	Yes	No	Good																	
Included	A	148	Refrigeration Room	Mechanical	Piping	Metal Cladded Pipe Insulation	High	No	No	No	Good	Non-suspect styrofoam insulating product.																
Included	A	148	Refrigeration Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	A	148	Refrigeration Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	149	Boiler Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	149	Boiler Room	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	149	Boiler Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	149	Boiler Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	149	Boiler Room	Mechanical	Caulking	Boiler Exhaust Caulking	High	No	Yes	No	Good		Bulk	A-034	30-May-17													
Included	A	149	Boiler Room	Mechanical	Rope Gasket	Boiler Rope Gasket	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	149	Boiler Room	Mechanical	Refractory Brick	Boiler Refractory Brick	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	149	Boiler Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-031, A-032, A-033, and A-035	30-May-17													
Included	A	149	Boiler Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	150	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	150	Electrical Room	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	150	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	150	Electrical Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	150	Electrical Room	Walls	Caulking	White Building Caulking	High	No	Yes	No	Good																	
Included	A	150	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	151	Generator Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	151	Generator Room	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	151	Generator Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	151	Generator Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	151	Generator Room	Walls	Caulking	Silver Generator Exhaust Caulking	High	No	Yes	No	Good		Bulk	A-036	30-May-17													
Included	A	151	Generator Room	Mechanical	Piping	Metal Cladded Pipe Insulation	High	No	No	No	Good	Non-suspect fibreglass insulating product.																
Included	A	151	Generator Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	A	152	Communications Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	152	Communications Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	152	Communications Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	152	Communications Room	Walls	Caulking	Silver Generator Exhaust Caulking	High	No	Yes	No	Good																	
Included	A	152	Communications Room	Mechanical	Firestop	White Firestop	High	No	Yes	No	Good																	
Included	A	153	Hallway	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	153	Hallway	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	153	Hallway	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	153	Hallway	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	A	153	Hallway	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	A	153	Hallway	Mechanical	Firestop	Red Firestop	High	No	Yes	No	Good																	
Included	A	153	Hallway	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	25 ft	Photograph 2	Door Jamb
Included	A	153	Hallway	Mechanical	Duct Work	Silver Duct Mastic	High	No	Yes	No	Good																	
Included	A	154, 155, and 156	Lounge	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	154, 155, and 156	Lounge	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	154, 155, and 156	Lounge	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	154, 155, and 156	Lounge	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	A	154, 155, and 156	Lounge				High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	A	154, 155, and 156	Lounge	Ceiling	Ceiling	2'x4' Textured Ceiling Tile	High	No	No	No	Good																	
Included	A	154, 155, and 156	Lounge	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	A-018	30-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	15 ft	Photograph 2	Door Jamb
Included	A	154, 155, and 156	Lounge	Plumbing	Sink	Gold Sink Undercoat	High	Yes	Yes	Yes	Good		Bulk	VS A-005	30-May-17	Chrysotile	Sink Undercoat	0.50%	No	No	No	Annually	5	Moderate	Manage in place	1 Sink	Photograph 1	Door Jamb
Included	A	158	Storage Room	Walls	Floor	Block Walls	High	No	No	No	Good																	
Included	A	158	Storage Room	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	A	158	Storage Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	159	Hallway	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	159	Hallway	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	A	159	Hallway	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	159	Hallway	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	A	162	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	162	Storage Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	162	Storage Room	Floor	Floor	Blue and White Streaked Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	162	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	163	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	163	Storage Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	163	Storage Room	Floor	Floor	Blue and White Streaked Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	A	163	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	165	Ice Cleaner Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	165	Ice Cleaner Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	165	Ice Cleaner Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	165	Ice Cleaner Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	A	172, 173, 174, and 175	Dressing Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	172, 173, 174, and 175	Dressing Room	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	A	172, 173, 174, and 175	Dressing Room	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	172, 173, 174, and 175	Dressing Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	172, 173, 174, and 175	Dressing Room	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	A	176	Hallway	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	A	176	Hallway	Floor	Floor	Rubber	High	No	No	No	Good																	
Included	A	176	Hallway	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	A	177	Laundry Room	Walls	Walls	Block																						

Appendix C
Sasktel Centre
ACM Inventory

Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	A	194, 195, 196, and 197	Suite Lounge and Bar	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	A	194, 195, 196, and 197	Suite Lounge and Bar	Floor	Floor	New Floor Tile	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	A	194, 195, 196, and 197	Suite Lounge and Bar	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good																	
Included	A	194, 195, 196, and 197	Suite Lounge and Bar	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good		Bulk	A-017	30-May-17													
Included	A	198	Concourse	Walls	Walls	Block Walls	High	No	Yes	No	Good																	
Included	A	198	Concourse	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	198	Concourse	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	198	Concourse	Mechanical	Firestop	Rad Firestop	High	No	Yes	No	Good																	
Included	A	199A	Concourse	Walls	Walls	Concrete	High	No	Yes	No	Good																	
Included	A	199A	Concourse	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	199A	Concourse	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	A	199A	Concourse	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	A	199A	Concourse	Mechanical	Duct Work	White Duct Tape	High	No	No	No	Good	New non-suspect duct tape.																
												Non-suspect clamped joints of PVC lines.																
Included	A	199A	Concourse	Mechanical	Drain Lines	Drain Lines	High	No	No	No	Good	New non-suspect duct connector fabric.																
Included	A	199A	Concourse	Mechanical	Duct Work	Connector Fabric	High	No	No	No	Good																	
Included	A	199B	Storage Room	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	A	199B	Storage Room	Walls	Walls	Plywood with Compound	High	No	Yes	No	Good																	
Included	A	199B	Storage Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	A	199B	Storage Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Floor	Floor	Underside of Arena Level Ceilings	High	No	Yes	No	Good																	
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Floor	Floor	Metal	High	No	No	No	Good																	
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Mechanical	Firestop	Red Firestop	High	No	Yes	No	Good		Bulk	A-062	30-May-17													
												Non-suspect clamped joints of PVC lines.																
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Mechanical	Duct Work	Connector Fabric	High	No	No	No	Good	New non-suspect duct connector fabric.																
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Mechanical	Duct Work	Grey Duct Mastic	High	No	Yes	No	Good																	
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	600 ft	Photograph 2	Door Jamb
												Pipe-run insulation observed to be non-suspect fibreglass throughout the ceiling spaces.																
Included	C	Arena Level Ceiling Space	Arena Level Ceiling Space	Mechanical	Piping	Pipe-Run Insulation	High	No	No	No	Good																	
Included	C	200	Hallway	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	200	Hallway	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	200	Hallway	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	200	Ticket Booth	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	200	Ticket Booth	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	200	Ticket Booth	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	200	Ticket Booth	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	General Office	General Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	General Office	General Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	General Office	General Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good																	
Included	C	202	Washroom	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	202	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	202	Washroom	Floor	Floor	New Floor Tile	High	No	No	No	Good																	
Included	C	202	Washroom	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good																	
Included	C	203	Office Area	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	203	Office Area	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	203	Office Area	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	203	Office Area	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good																	
Included	C	204A	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	204A	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	204A	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good																	
Included	C	204A	Office	Windows	Caulking	Rubber Window Caulking	High	No	No	No	Good																	
Included	C	204B	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-044	30-May-17													
Included	C	204B	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	204B	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good		Bulk	A-043	30-May-17													
Included	C	204B	Office	Windows	Caulking	Rubber Window Caulking	High	No	No	No	Good																	
Included	C	205A	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	205A	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	205A	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good																	
Included	C	205A	Office	Windows	Caulking	Rubber Window Caulking	High	No	No	No	Good																	
Included	C	205B	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	205B	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	205B	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good																	
Included	C	205B	Office	Windows	Caulking	Rubber Window Caulking	High	No	No	No	Good																	
Included	C	205C	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	205C	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	205C	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	205C	Office	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	205C	Office	Windows	Caulking	Rubber Window Caulking	High	No	No	No	Good																	
Included	C	206	Office Area	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	206	Office Area	Walls	Walls	Metal	High	No	No	No	Good																	
Included	C	206	Office Area	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	C	206	Office Area	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring	High	No	Yes	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	206	Office Area	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good																	
Included	C	206	Office Area	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	206	Office Area	Plumbing	Sink	Gold Sink Undercoat	High	Yes	Yes	Yes	Good		Bulk	VS A-005	30-May-17	Chrysotile	Sink Undercoat	0.50%	No	No	No	Annually	5	Moderate	Manage in place	2 Sinks	Photograph 1	Door Jamb
Included	C	207A																										

Appendix C
Sasktel Centre
ACM Inventory

Included/Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	C	210	Ticket Booth	Ceiling	Ceiling	2'x4' Ceiling Tile with Widthwise Fissures	High	No	Yes	No	Good		Bulk	A-039 and A-040	30-May-17													
Included	C	210	Ticket Booth	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	5 ft	Photograph 2	Door Jamb
Included	C	211	Lobby	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	C	211	Lobby	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	211	Lobby	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	211	Lobby	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	211	Lobby	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect fibreglass insulating product.																
Included	C	212	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	212	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	212	Electrical Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	212	Electrical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect PVC fittings.																
Included	C	212	Electrical Room	Mechanical	Firestop	Red Firestop	High	No	Yes	No	Good	Non-suspect fibreglass insulating product.																
Included	C	212	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	213	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	213	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	213	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	C	214	Janitor Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	214	Janitor Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	214	Janitor Room	Ceiling	Ceiling	Plywood	High	No	No	No	Good																	
Included	C	214	Janitor Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-038	30-May-17													
Included	C	214	Janitor Room	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	5 ft	Photograph 2	Door Jamb
Included	C	215	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	215	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	215	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-037	30-May-17													
Included	C	216	Concession	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	216	Concession	Floor	Floor	Beige Vinyl Sheet Flooring with Turquoise and Red Speckles	High	No	Yes	No	Good																	
Included	C	216	Concession	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	217	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	217	Storage Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	217	Storage Room	Floor	Floor	Beige Vinyl Sheet Flooring with Turquoise and Red Speckles	High	No	Yes	No	Good																	
Included	C	217	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	217	Storage Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	218A	First Aid Office	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	218A	First Aid Office	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring	High	No	Yes	No	Good																	
Included	C	218A	First Aid Office	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	C	218A	First Aid Office	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	C	219A	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	219A	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	219A	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-057	30-May-17													
Included	C	219B	Janitor Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	219B	Janitor Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	219B	Janitor Room	Ceiling	Ceiling	Unfinished Drywall	High	No	No	No	Good																	
Included	C	219B	Janitor Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	C	219B	Janitor Room	Mechanical	Duct Work	Grey Duct Mastic	High	No	Yes	No	Good																	
Included	C	220A	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	220A	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	220A	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	C	220B	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	220B	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	220B	Electrical Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-055	30-May-17													
Included	C	220B	Electrical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-056	30-May-17													
Included	C	221A	Concession	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	221A	Concession	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	221A	Concession	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	221B	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	221B	Storage Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	221B	Storage Room	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	221B	Storage Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	221B	Storage Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	221C	Bar	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	221C	Bar	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	221C	Bar	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	221C	Bar	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect PVC and fibreglass fittings.																
Included	C	221C	Bar	Mechanical	Drain Lines	Drain Lines	High	No	No	No	Good	Non-suspect clamped joints or PVC lines.																
Included	C	223	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	223	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	223	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	C	225	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	225	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	226	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-054	30-May-17													
Included	C	226	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	226	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	226	Electrical Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	226	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	Lobby adjacent to Room 226	Lobby	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 226	Lobby	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 226	Lobby	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 226	Lobby	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	Lobby adjacent to Room 226	Lobby	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good																	
Included	C	227	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	227	Washroom	Floor	Floor																							

Appendix C
Sasktel Centre
ACM Inventory

Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	C	229	Janitor Room	Mechanical	Drain Lines	Drain Lines	High	No	No	No	Good	Non-suspect clamped joints or PVC lines.																
Included	C	230	Washroom	Walls	Floor	Block Walls	High	No	No	No	Good																	
Included	C	230	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	230	Washroom	Ceiling	Ceiling	2'x2' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	C	231	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	231	Washroom	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	C	231	Washroom	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	C	231	Washroom	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	231	Washroom	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	232	Concession	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	232	Concession	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	C	232	Concession	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	235	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	C	235	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	235	Washroom	Ceiling	Ceiling	2'x2' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good	Non-suspect fibreglass insulating product.																
Included	C	235	Washroom	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good																	
Included	C	236A	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	236A	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	236A	Washroom	Ceiling	Ceiling	2'x2' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	C	236A	Washroom	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect fibreglass insulating product.																
Included	C	236B	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	236B	Storage Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	236B	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-053	30-May-17													
Included	C	236B	Storage Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	237A	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	237A	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	237A	Washroom	Ceiling	Ceiling	2'x2' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	C	237A	Washroom	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect fibreglass insulating product.																
Included	C	237B	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	237B	Storage Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	237B	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	237B	Storage Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect fibreglass insulating product.																
Included	C	Lobby adjacent to Room 237B	Lobby	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 237B	Lobby	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 237B	Lobby	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 237B	Lobby	Ceiling	Ceiling	Drywall Ceiling Tiles	High	No	No	No	Good																	
Included	C	Lobby adjacent to Room 237B	Lobby	Windows	Caulking	Black Window Caulking	High	No	No	No	Good		Bulk	A-052	30-May-17													
Included	C	238	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	238	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	238	Washroom	Ceiling	Ceiling	2'x2' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	C	238	Washroom	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good	Non-suspect fibreglass insulating product.																
Included	C	239	Bar	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	239	Bar	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	C	239	Bar	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	240A	Concession	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	240A	Concession	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	C	240A	Concession	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	241	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	241	Storage Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	241	Storage Room	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	C	241	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-051	30-May-17													
Included	C	242	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	242	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	242	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	C	243	Mechanical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	243	Mechanical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	243	Mechanical Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	243	Mechanical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good		Bulk	A-049	30-May-17													
Included	C	244	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	244	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	244	Washroom	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-050	30-May-17													
Included	C	245	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	245	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	245	Electrical Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-048	30-May-17													
Included	C	245	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	C	246	Lobby	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	246	Lobby	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	246	Lobby	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	C	246	Lobby	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good																	
Included	C	247	Concourse	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	247	Concourse	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	247	Concourse	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	247	Concourse	Ceiling	Ceiling	Spray-Applied Fireproofing	High	No	Yes	No	Good																	
Included	C	247	Concourse	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	247	Concourse	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	C	247	Concourse	Ceiling	Ceiling	1'x1' Ceiling Tile with Long Fissures	High	No	Yes	No	Good		Bulk	A-063, A-064, and A-065	30-May-17													
Included	C	247	Concourse	Mechanical	Duct Work	Grey Duct Mastic	High	No	Yes	No	Good																	
Included	C	250	Suite	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	250	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	C	250	Suite	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	C	250	Suite	Ceiling	Ceiling	Ceiling Tile	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	C	251	Suite	Walls	Walls																							

Appendix C
Sasktel Centre
ACM Inventory

	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	C	253	Suite	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	C	253	Suite	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	C	253	Suite	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	C	CS274	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	CS274	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	CS274	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	CS275	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	CS275	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	CS275	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	CS276	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-058	30-May-17													
Included	C	CS276	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	CS276	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	CS277	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-060	30-May-17													
Included	C	CS277	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	CS277	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	CS278	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	CS278	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	CS278	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	CS279	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	C	CS279	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
												Date coded to a time period where asbestos use was not widespread.																
Included	C	CS279	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good																	
Included	C	CS286	Suite																									

Appendix C
Sasktel Centre
ACM Inventory

[illegible]

Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	M	305	Meeting Room	Windows	Caulking	Black Window Caulking	High	Yes	Yes	Yes	Good	Located on the inside of the exterior windows.	Bulk	VS A-089	31-May-17	Chrysotile	Window Caulking	1.80%	No	No	No	Annually	5	Moderate	Manage in place	225 ft	Photograph 3	Door Jamb
Included	M	306	Bar	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	306	Bar	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	306	Bar	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	306	Bar	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	M	307	Loft Lounge	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	307	Loft Lounge	Walls	Walls	Fibreglass Panels	High	No	No	No	Good																	
Included	M	307	Loft Lounge	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	307	Loft Lounge	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	307	Loft Lounge	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	307	Loft Lounge	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	M	308	Office	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	308	Office	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	308	Office	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	M	308	Office	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	308	Office	Windows	Caulking	Black Window Caulking	High	Yes	Yes	Yes	Good	Located on the inside of the exterior windows.	Bulk	VS A-089	31-May-17	Chrysotile	Window Caulking	1.80%	No	No	No	Annually	5	Moderate	Manage in place	260 ft	Photograph 3	Door Jamb
Included	M	310	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	310	Electrical Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	310	Electrical Room	Mechanical	Firestop	Red Firestop	High	No	Yes	No	Good																	
Included	M	310	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	M	312	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	312	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	312	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-082	31-May-17													
Included	M	313	Lobby	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	313	Lobby	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	313	Lobby	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	313	Lobby	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good																	
Included	M	3.13.01	Office Lobby	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	3.13.01	Office Lobby	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	M	3.13.01	Office Lobby	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	M	3.13.01	Office Lobby	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good		Bulk	A-090	31-May-17													
Included	M	314 and 314A	Concession	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	314 and 314A	Concession	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	314 and 314A	Concession	Floor	Floor	Concrete Coating	High	No	No	No	Good																	
Included	M	314 and 314A	Concession	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	315	Lobby	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	315	Lobby	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	315	Lobby	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	315	Lobby	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good																	
Included	M	316	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	316	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	316	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Floor	Floor	Metal	High	No	No	No	Good																	
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Mechanical	Piping	Pipe-Fitting Insulation	High	No	Yes	No	Good																	
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good	New non-suspect duct connector fabric.	Bulk	A-083	31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	10 ft	Photograph 2	Door Jamb
Included	M	Mechanical Room adjacent to S5	Mechanical Room	Mechanical	Duct Work	Connector Fabric	High	No	No	No	Good																	
Included	M	317	Washroom	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	317	Washroom	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring with Red and Turquoise Spots	High	No	No	No	Good																	
Included	M	317	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	318	Washroom	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	318	Washroom	Floor	Floor	Beige Mosaic Vinyl Sheet Flooring with Red and Turquoise Spots	High	No	Yes	No	Good		Bulk	A-084	31-May-17													
Included	M	318	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	319	Storage Room	Walls	Walls	Unfinished Drywall	High	No	No	No	Good																	
Included	M	319	Storage Room	Walls	Walls	Fibreglass Panels	High	No	No	No	Good																	
Included	M	319	Storage Room	Floor	Floor	Metal	High	No	No	No	Good																	
Included	M	319	Storage Room	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	Storage Room adjacent to Room 320	Storage Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	Storage Room adjacent to Room 320	Storage Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	Storage Room adjacent to Room 320	Storage Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-085	31-May-17													
Included	M	322	Electrical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	322	Electrical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	322	Electrical Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	322	Electrical Room	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	M	323	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	323	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	323	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-086	31-May-17													
Included	M	Janitor Room adjacent to Room 323	Janitor Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	Janitor Room adjacent to Room 323	Janitor Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	Janitor Room adjacent to Room 323	Janitor Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	324	Mechanical Room	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	324	Mechanical Room	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	324	Mechanical Room	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	324	Mechanical Room	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	324	Mechanical Room	Mechanical	Duct Work	Red/Brown Duct Mastic	High	Yes	Yes	Yes	Good		Bulk	VS A-018 and A-083	30-May-17 and 31-May-17	Chrysotile	Duct Mastic	0.75% to 1.3%	No	No	No	Annually	5	Low	Manage in place	20 ft	Photograph 2	Door Jamb
Included	M	325	Washroom	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	325	Washroom	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	325	Washroom	Ceiling	Ceiling	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	326	Washroom																									


Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	M	332	Open Area	Walls	Walls	Fibreglass Panels	High	No	No	No	Good																	
Included	M	332	Open Area	Walls	Walls	Concrete	High	No	No	No	Good																	
Included	M	332	Open Area	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	332	Open Area	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	332	Open Area	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	332	Open Area	Mechanical	Duct Work	Grey Duct Mastic	High	No	Yes	No	Good																	
Included	M	333	Halfway	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	333	Halfway	Floor	Floor	Ceramic Tile	High	No	No	No	Good																	
Included	M	333	Halfway	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	333	Halfway	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good	Non-suspect fibreglass insulating product.																
Included	M	333	Halfway	Mechanical	Piping	Pipe-Fitting Insulation	High	No	No	No	Good																	
Included	M	CS308A	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	CS308A	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	M	CS308A	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	M	CS308A	Suite	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	M	CS340	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	CS340	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	M	CS340	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Small Pinholes and Small Divots	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	M	CS340	Suite	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	M	CS341	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	M	CS341	Suite	Floor	Floor	Carpet	High	No	No	No	Good																	
Included	M	CS341	Suite	Ceiling	Ceiling	2'x4' Ceiling Tile with Circular Patterned Fissures	High	No	No	No	Good	Date coded to a time period where asbestos use was not widespread.																
Included	M	CS341	Suite	Plumbing	Sink	White Sink Undercoat	High	No	Yes	No	Good																	
Included	M	Concourse	Concourse	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-096 and A-097	31-May-17													
Included	M	Concourse	Concourse	Walls	Walls	Block Walls	High	No	No	No	Good																	
Included	M	Concourse	Concourse	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	M	Concourse	Concourse	Ceiling	Ceiling	Concrete	High	No	No	No	Good																	
Included	M	Concourse	Concourse	Ceiling	Ceiling	Spray-Applied Fireproofing	High	No	Yes	No	Good		Bulk	A-091, A-092, A-093, A-094, and A-095	31-May-17													
Included	G	401	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	401	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	401	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	401	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-068 and A-069	31-May-17													
Included	G	402	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	402	Suite	Floor	Floor	Wood	High	No	No	No	Good																	
Included	G	402	Suite	Ceiling	Ceiling	New Laminate	High	No	No	No	Good																	
Included	G	402	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Long Fissures	High	No	Yes	No	Good																	
Included	G	403	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	403	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	403	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	403	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Long Fissures	High	No	Yes	No	Good																	
Included	G	404	Lounge	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	404	Lounge	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	404	Lounge	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	404	Lounge	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	G	405	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	405	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	405	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	405	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-070	31-May-17													
Included	G	406	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	406	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	406	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	406	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good																	
Included	G	407	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good		Bulk	A-072	31-May-17													
Included	G	407	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	407	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	407	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Small Pinholes and Small Divots	High	No	Yes	No	Good		Bulk	A-071	31-May-17													
Included	G	408	Suite	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	408	Suite	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	408	Suite	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	408	Suite	Ceiling	Ceiling	1'x1' Ceiling Tile with Long Fissures	High	No	Yes	No	Good																	
Included	G	409	Halfway	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	409	Halfway	Walls	Walls	Pre-Fabricated Panels	High	No	No	No	Good																	
Included	G	409	Halfway	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	409	Halfway	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	G	409	Halfway	Mechanical	Duct Work	Silver Duct Mastic	High	No	Yes	No	Good		Bulk	A-067	31-May-17													
Included	G	409	Halfway	Mechanical	Duct Work	Grey Duct Mastic	High	No	Yes	No	Good		Bulk	A-066	31-May-17													
Included	G	409	Halfway	Electrical	Electrical Panels and Components	Electrical Panels and Components	High	Yes	No	Potential	Good	Not sampled due to safety concerns.							No	No		Annually		Low	Inspect and sample if scheduled for removal.			
Included	G	410	Booth	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	410	Booth	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	410	Booth	Walls	Walls	Pre-Fabricated Panels	High	No	No	No	Good																	
Included	G	410	Booth	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	410	Booth	Ceiling	Ceiling	Metal	High	No	Yes	No	Good																	
Included	G	411	Booth	Walls	Walls	Drywall Joint Compound	High	No	Yes	No	Good																	
Included	G	411	Booth	Walls	Walls	Wood	High	No	No	No	Good																	
Included	G	411	Booth	Walls	Walls	Pre-Fabricated Panels	High	No	No	No	Good																	
Included	G	411	Booth	Floor	Floor	New Laminate	High	No	No	No	Good																	
Included	G	411	Booth	Ceiling	Ceiling	Metal	High	No	Yes	No	Good																	
Included	N/A	Main Elevator	Elevator	Walls	Walls	Wood	High	No	No	No	Good																	
Included	N/A	Main Elevator	Elevator	Floor	Floor	Metal	High	No	No	No	Good																	
Included	N/A	Main Elevator	Elevator	Ceiling	Ceiling	Metal	High	No	No	No	Good																	
Included	N/A	SW 1	Stairwell	Walls	Walls	Concrete Scratch Coat	High	No	Yes	No	Good		Bulk	A-073, A-074, A-075, and A-076	31-May-17													
Included	N/A	SW 1	Stairwell	Floor	Floor	Concrete	High	No	No	No	Good																	
Included	N/A	SW 1	Stairwell	Floor	Floor	Ceramic Tile	High																					

Appendix C Sasktel Centre ACM Inventory																												
Included/ Excluded	Floor	Room #	Area Description	Elements	Subelements	Material Description	Accessibility	Suspect?	Sampled?	Asbestos Containing Material?	Condition	Field Notes	Sample Type	Sample ID	Sample Date	Asbestos Type	ACM Product	% of asbestos	Friable	Sprayed-on	Maintenance	Inspection	Priority	Potential for Disturbance	Recommended Action	Quantity	Photograph ID	Labelling Type
Included	N/A	Exterior	Exterior	Walls	Walls	Stucco	High	No	Yes	No	Good		Bulk	A-099, A-100, A-101, A-102, A-103, A-104, and A-105	31-May-17													
Included	N/A	Exterior	Exterior	Walls	Caulking	Gray Building Caulking	High	No	Yes	No	Good		Bulk	A-108	31-May-17													
Included	N/A	Exterior	Exterior	Windows	Caulking	Black Window Caulking	High	No	Yes	No	Good		Bulk	A-106 and A- 107	31-May-17													
Included	N/A	Exterior	Exterior	Windows	Caulking	White Window Frame Caulking	High	No	Yes	No	Good		Bulk	A-109	31-May-17													
Excluded	A	103	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction. Access to area was not provided/area was under renovation/construction.																
Excluded	A	133	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	134	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	137	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	140	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	166	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	167	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	168	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	169	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	170	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	171	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	186	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	187	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	188	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	189	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	190	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	A	191	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	C	218B	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	C	221D	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	C	222	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	C	224	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	C	233	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	C	240B	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	M	301B	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	M	302	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	M	311	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	M	320	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	M	321	N/A	Entire Room	Entire Room	N/A	N/A	N/A	N/A	N/A	N/A	Access to area was not provided/area was under renovation/construction.																
Excluded	G	Areas Outside of the Main Gondola Level Walkway	Areas outside of the main walkway	Entire Area	Entire Area	N/A	N/A	N/A	N/A	N/A	N/A	Access to the entire area was not provided due to safety concerns.																
Excluded	N/A	Elevator 2	N/A	Elevator	Elevator	N/A	N/A	N/A	N/A	N/A	N/A	Access to the Elevator was not provided.																
Excluded	M	Areas Outside of the Main Walkway	Mechanical Room Adjacent S5	Entire Area	Entire Area	N/A	N/A	N/A	N/A	N/A	N/A	Room assessed from the walkway only.																
Excluded	A	Arena Level Ceiling Space	Arena Level Ceiling Space	Entire Area	Entire Area	N/A	N/A	N/A	N/A	N/A	N/A	Room assessed from the walkway only.																



APPENDIX D

Floor Plans



NOTE(S)

1. ASBESTOS IS A CARCINOGEN. AVOID BREATHING ASBESTOS DUST.
2. ASBESTOS-CONTAINING RED / BROWN DUCT MASTIC IS SUSPECTED TO BE LOCATED ON DUCT WORK THROUGHOUT THE SITE.
3. SAMPLE A-062 WAS COLLECTED WITHIN THE ARENA LEVEL CEILING SPACE.
4. SAMPLES A-099 TO A-109 WERE COLLECTED ALONG THE EXTERIOR OF THE BUILDING.

LEGEND

	ASBESTOS - CONTAINING SAMPLE LOCATION
	ASBESTOS - CONTAINING DUCT MASTIC
	ASBESTOS - CONTAINING SINK UNDERCOAT
	ASBESTOS - CONTAINING SINK UNDERCOAT AND DUCT MASTIC

REFERENCE(S)

PLAN OBTAINED FROM INFRASTRUCTURE SERVICES DEPARTMENT CITY OF SASKATOON. DATED BY 11/10/2005.

CLIENT
CITY OF SASKATOON

CONSULTANT




YYYY-MM-DD	2017-07-10
DESIGNED	KH
PREPARED	YAW
REVIEWED	KH
APPROVED	AG

PROJECT
ASBESTOS ASSESSMENT
SASKTEL CENTRE
3515 THATCHER AVENUE
TITLE
ARENA LEVEL

PROJECT NO.	CONTROL	REV.	FIGURE
1667963	1000-HM-0001	0	1

SCHEMATIC ONLY, NOT TO SCALE





IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: ANSI A 26 mm



NOTE(S)

1. ASBESTOS IS A CARCINOGEN. AVOID BREATHING ASBESTOS DUST.
2. ASBESTOS-CONTAINING RED / BROWN DUST MASTIC IS SUSPECTED TO BE LOCATED ON DUCT WORK THROUGHOUT THE SITE.
3. SAMPLE A-062 WAS COLLECTED WITHIN THE ARENA LEVEL CEILING SPACE.
4. SAMPLES A-099 TO A-109 WERE COLLECTED ALONG THE EXTERIOR OF THE BUILDING.

LEGEND

- | | | |
|---|---|--|
|  | # | ASBESTOS - CONTAINING SAMPLE LOCATION |
|  | | ASBESTOS - CONTAINING DUCT MASTIC |
|  | | ASBESTOS - CONTAINING SINK UNDERCOAT |
|  | | ASBESTOS - CONTAINING SINK UNDERCOAT AND DUCT MASTIC |

REFERENCE(S)

PLAN OBTAINED FROM INFRASTRUCTURE SERVICES DEPARTMENT CITY OF SASKATOON. DATED BY 11/10/2005.

CLIENT
CITY OF SASKATOON

CONSULTANT

YYYY-MM-DD 2017-07-10

DESIGNED KH

PREPARED	YAW
----------	-----

REVIEWED KH

APPROVED AG

SCHEMATIC ONLY, NOT TO SCALE


PROJECT
ASBESTOS ASSESSMENT
SASKTEL CENTRE
3515 THATCHER AVENUE

TITLE
CONCOURSE LEVEL


PROJECT NO.
1667963

CONTROL
1000-HM-0002

REV.
0FIGURE
2



IF THIS MEASUREMENT DOES NOT MATCH WHAT IS SHOWN, THE SHEET SIZE HAS BEEN MODIFIED FROM: ANSI A
25 mm



NOTE(S)

1. ASBESTOS IS A CARCINOGEN. AVOID BREATHING ASBESTOS DUST.
2. ASBESTOS-CONTAINING RED / BROWN DUCT MASTIC IS SUSPECTED TO BE LOCATED ON DUCT WORK THROUGHOUT THE SITE.
3. SAMPLE A-062 WAS COLLECTED WITHIN THE ARENA LEVEL CEILING SPACE.
4. SAMPLES A-099 TO A-109 WERE COLLECTED ALONG THE EXTERIOR OF THE BUILDING.

LEGEND

- ASBESTOS - CONTAINING SAMPLE LOCATION
- ASBESTOS - CONTAINING DUCT MASTIC
- ASBESTOS - CONTAINING SINK UNDERCOAT
- ASBESTOS - CONTAINING SINK UNDERCOAT AND DUCT MASTIC

REFERENCE(S)

PLAN OBTAINED FROM INFRASTRUCTURE SERVICES DEPARTMENT CITY OF SASKATOON. DATED BY 12/10/2005.

CLIENT
CITY OF SASKATOON

CONSULTANT



YYYY-MM-DD 2017-07-10

DESIGNED KH

PREPARED YAW

REVIEWED KH

APPROVED AG

SCHEMATIC ONLY, NOT TO SCALE

PROJECT
ASBESTOS ASSESSMENT
SASKTEL CENTRE
3515 THATCHER AVENUE

TITLE
GONDOLA LEVEL

PROJECT NO.
1667963

CONTROL
1000-HM-0004

REV.
0

FIGURE
4

As a global, employee-owned organisation with over 50 years of experience, Golder Associates is driven by our purpose to engineer earth's development while preserving earth's integrity. We deliver solutions that help our clients achieve their sustainable development goals by providing a wide range of independent consulting, design and construction services in our specialist areas of earth, environment and energy.

For more information, visit golder.com

Africa	+ 27 11 254 4800
Asia	+ 86 21 6258 5522
Australasia	+ 61 3 8862 3500
Europe	+ 356 21 42 30 20
North America	+ 1 800 275 3281
South America	+ 56 2 2616 2000

solutions@golder.com
www.golder.com

Golder Associates Ltd.
16820 107 Avenue
Edmonton, Alberta, T5P 4C3
Canada
T: +1 (780) 483 3499

