

A photograph showing a construction worker in a trench. The worker is wearing a blue long-sleeved shirt, orange safety shorts, and grey rubber boots. They are operating a trencher, a machine with a rotating cutting wheel, to cut a new pipe into the ground. A large, light blue pipe is being laid along the trench. The ground is sandy and uneven. The text "Water Main Repair Methods and Techniques" is overlaid in the center of the image.

Water Main Repair Methods and Techniques

Water Service Disruption Report

Are prioritized then submitted to Clearances and Locations Work Group.

City of Saskatoon - Water Service Disruption Report Memo # _____

Location: _____ WRR #: _____

Call to Dispatch: _____ Time Dispatched: _____ Arrival Time: _____ Completion Time: _____

Crew Members: _____; Date Initiated: _____; Outage Notification Given: ____ Yes; ____ No;

Type of Interruption		Units Affected (Number without service)	
Water Main: _____	Valve: _____	Houses: _____	Comments: _____
Water Conn: _____	Hydrant: _____	Apartments: _____	Comments: _____
Curb Stop: _____ (M/S _____; P/S _____; C/S _____)	Sched. _____	Sched. _____	Comments: _____
Curb Box: Raise _____; Lower _____	Business: _____	Business: _____	Type: _____
Primary Main: _____	Private Leak: _____	Other: _____	
Primary Valve: _____	Frozen Conn: _____		

Valves out of Service			
VALVES OPERATED	Valve	Off	Crew
Location of Valve	GIS No.	YYMMDD	Time

Hydrants out of Service	Hydrant	Off	Crew	On	Crew
Location of Hydrant	GIS No.	YYMMDD	Time	Initials	YYMMDD

Connection drawings for: _____

Excavation Obstruction		Additional Information Required:	
Tree: _____	Comments: _____	Correlation Required: _____	Yes; ____ No; ____
Utility Pole: _____	Comments: _____	Slow Leak: _____	Yes; ____ No; ____
Fence: _____	Comments: _____	Hydro Excavate: _____	Yes; ____ No; ____
Vehicle: _____	Comments: _____	Washout Visible: _____	Yes; ____ No; ____
Pavement: _____	Concrete: _____; Paving Stone: _____	Broke into Sanitary Main: _____	Yes; ____ No; ____
Other: _____		Broke into Storm Main: _____	Yes; ____ No; ____

Temporary Water Provision		Traffic Controls:	
Water Trailer: _____	(On Site); _____ (Arranged For);	Detour Required: _____	Yes; ____ No; ____
Temporary Connection: _____	(Installed); _____ (Arranged For);	Bus Route: _____	Yes; ____ No; ____
From: _____	To: _____	Post for No Parking: _____	Yes; ____ No; ____
Fill-up: _____	(Time On): _____ (Time Off): _____		

- # Water Service Disruption Report
- Are prioritized then submitted to Clearances and Locations Work Group.
- City of Saskatoon - Water Service Disruption Report** Memo # _____
- Location: _____ WRR #: _____
- Call to Dispatch: _____ Time Dispatched: _____ Arrival Time: _____ Completion Time: _____
- Crew Members: _____; Date Initiated: _____; Outage Notification Given: ____ Yes; ____ No;
- | Type of Interruption | | Units Affected (Number without service) | |
|--|---------------------|---|-----------------|
| Water Main: _____ | Valve: _____ | Houses: _____ | Comments: _____ |
| Water Conn: _____ | Hydrant: _____ | Apartments: _____ | Comments: _____ |
| Curb Stop: _____ (M/S _____; P/S _____; C/S _____) | Sched. _____ | Sched. _____ | Comments: _____ |
| Curb Box: Raise _____; Lower _____ | Business: _____ | Business: _____ | Type: _____ |
| Primary Main: _____ | Private Leak: _____ | Other: _____ | |
| Primary Valve: _____ | Frozen Conn: _____ | | |
- | Valves out of Service | | | |
|-----------------------|---------|--------|------|
| VALVES OPERATED | Valve | Off | Crew |
| Location of Valve | GIS No. | YYMMDD | Time |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
- | Hydrants out of Service | Hydrant | Off | Crew | On | Crew |
|-------------------------|---------|--------|------|----------|--------|
| Location of Hydrant | GIS No. | YYMMDD | Time | Initials | YYMMDD |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
- Connection drawings for: _____
- _____
- | Excavation Obstruction | | Additional Information Required: | |
|------------------------|--------------------------------------|----------------------------------|--------------------|
| Tree: _____ | Comments: _____ | Correlation Required: _____ | Yes; ____ No; ____ |
| Utility Pole: _____ | Comments: _____ | Slow Leak: _____ | Yes; ____ No; ____ |
| Fence: _____ | Comments: _____ | Hydro Excavate: _____ | Yes; ____ No; ____ |
| Vehicle: _____ | Comments: _____ | Washout Visible: _____ | Yes; ____ No; ____ |
| Pavement: _____ | Concrete: _____; Paving Stone: _____ | Broke into Sanitary Main: _____ | Yes; ____ No; ____ |
| Other: _____ | Bld: _____ | Broke into Storm Main: _____ | Yes; ____ No; ____ |
- | Temporary Water Provision | | Traffic Controls: | |
|-----------------------------|------------------------------------|----------------------------|--------------------|
| Water Trailer: _____ | (On Site); _____ (Arranged For); | Detour Required: _____ | Yes; ____ No; ____ |
| Temporary Connection: _____ | (Installed); _____ (Arranged For); | Bus Route: _____ | Yes; ____ No; ____ |
| From: _____ | To: _____ | Post for No Parking: _____ | Yes; ____ No; ____ |
| Fill-up: _____ | (Time On): _____ (Time Off): _____ | | |

Water Service Disruption Report

Are prioritized then submitted to Clearances and Locations Work Group.

A

B

- Section A of the Water Service Disruption Report.

[illegible]

Water Service Disruption Report

- Section B of the Water Service Disruption Report.

Hydrants out of Service Location of Hydrant	Hydrant GIS No.	Off		Crew Initials	On		Crew Initials
		YYMMDD	Time		YYMMDD	Time	
Connection drawings for: _____							
Excavation Obstructions:				Additional Information Required:			
Tree: _____ Comments: _____				Correlation Required: _____ Yes; _____ No;			
Utility Pole: _____ Comments: _____				Slow Leak: _____ Yes; _____ No;			
Fence: _____ Comments: _____				Hydro Excavate: _____ Yes; _____ No;			
Vehicle: _____ Comments: _____				Washout Visible: _____ Yes; _____ No;			
Pavement: ____; Concrete: ____; Paving Stone: ____; Blvd: ____:				Broke into Sanitary Main: _____ Yes; _____ No;			
Other: _____				Broke into Storm Main: _____ Yes; _____ No;			
Temporary Water Provisions:				Traffic Controls:			
Water Trailer: _____ (On Site); _____ (Arranged For);				Detour Required: _____ Yes; _____ No;			
Temporary Connection: _____ (Installed); _____ (Arranged For);				Bus Route: _____ Yes; _____ No;			
From: _____; To: _____				Post for No Parking: _____ Yes; _____ No;			
Fill-up: _____ (Time On); _____ (Time Off); _____							
PROPERTY DAMAGE: Yes: _____; No _____;							
OTHER REMARKS / OBSERVATIONS:							
TWE 03/0401							

Clearances and Locations Work Group

- Provides: drawings, utility locations, location numbers and forms.
- Coordinates the removal of obstructions if required.



Daily Work Sheet

- The daily work sheet is created to provide other departments with the location of the Water & Sewer work being performed.

DATE: Friday May 9 - 03													
Water and Sewer Maintenance Section													
:W&SMT1													
STATUS	LOCATION:	REPAIR TYPE:	PRIORITY	JOB #	Loc:	ACTIVITY:	GL	SIGNING:	GIS	UTL>LOC:	STAFFING:		
Current	1006 Tiffin Crescent	Sanitary Connection	MBL	664	3112	5-6500	05-270	S/S			LABOURERS -	Parker/Klassen	
2nd	Massey Drive & Marr Avenue	Water Main	MP1	146	3114	5-6100	02-150	On Site			BACKHOE OPERATOR -	Dmytrowich - 2343	
Hold	175/303 Delaronde Road	Repair C/B Lead	MP1	775	3079	5-6710	07-310	On Site	27126		T/A OPERATORS -	Pingue	
Hold	Arnhem St. & McNaughton Avenue	Hydrant (McAvery)	MP2	243	3059	5-6300	02-160	On Site	23535				
Hold	Field House	Water Connection	MBL	49246	1724067	5-6410	02-170	Crew					
:W&SMT2													
STATUS	LOCATION:	REPAIR TYPE:	PRIORITY	JOB #	Loc:	ACTIVITY:	GL	SIGNING:	GIS	UTL>LOC:	STAFFING:		
Hold	Clarence Avenue - 8th St. - 9th St.	Water Main	MP1	146	3115	5-6100	02-150	S/S			LABOURERS -		
Hold	15 Moxon Crescent	Sanitary Connection	MBL	664	3108	5-6500	05-270	S/S			BACKHOE OPERATOR -		
			MBL								T/A OPERATORS -		
			MBL										
:W&SMT3													
STATUS	LOCATION:	REPAIR TYPE:	PRIORITY	JOB #	Loc:	ACTIVITY:	GL	SIGNING:	GIS	UTL>LOC:	STAFFING:		
Hold	Dudley Street	Sanitary Connection	FMP	46806	1724067	5-6100	17-596	N/A			LABOURERS -		
			MBL								BACKHOE OPERATOR -		
			MBL								T/A OPERATORS -		
Hold	8th Street Yard	Cleanup Yard	MBL	49195	1724067	5-6100	02-150	N/A					
:W&SMT4													
STATUS	LOCATION:	REPAIR TYPE:	PRIORITY	JOB #	Loc:	ACTIVITY:	GL	SIGNING:	GIS	UTL>LOC:	STAFFING:		
Hold	Isabella Street / Eastlake Avenue	Repair C/B Lead	MBL	48959	1724067	5-6710	07-310	S/S			LABOURERS -		
Hold	Isabella Street / Eastlake Avenue	Valve (WPL)	MP2	146	3031	5-6200	02-150	S/S	1168		BACKHOE OPERATOR -		
			MBL								T/A OPERATORS -		
			MBL										
DAY OFF/DO		VACATION:		SICK:				OTHER:		ADDITIONAL STAFFING:			
Ross, Young, Maskwa & Crews, Olchove,		Hilton, Swidzinski				Collins - Medical				Loader - Cousins @ Landfill -			
Priority Legend													
(MP1) Maintenance Priority - (MBL) Maintenance Backlog - (MPS) Maintenance Program Support - (FMP) Funded Maintenance Program													
Pending Water & Sewer Work													
STATUS	LOCATION:	REPAIR TYPE:	PRIORITY	JOB #	Loc:	ACTIVITY:	GL	SIGNING:	GIS				
Hold	Boychuck Dr. South of Taylor St.	Sanitary MH F&C	MBL	760	3010	5-6620	07-310	Crew	21925				
Hold	Boychuck Dr. South of Taylor St.	Sanitary MH F&C	MBL	760	3010	5-6620	07-310	Crew	21924				
Hold	4200 Block Taylor Street	Sanitary MH F&C	MBL	563		5-6620	05-260	Crew	8575				
Hold	412 Avenue C South	Sanitary Stop (C&S)	MP2	48237	1724067	5-6400	02-170	S/S					
Hold	213 Avenue I South	Sanitary Stop (C&S)	MP2	48150	1724067	5-6400	02-170	S/S					
Hold	4th Avenue & 23th Street	Sanitary Top	MBL	573	3012	5-6620	05-260	S/S	3813				
Hold	Ottawa Avenue / 20th Street	San Bev Top	FMP	573	3068	5-6620	05-260	S/S	3231				

Daily Work Sheet Section A

- Section A shows the tasks for each Supervisor IV.

DATE: Friday May 9 - 03							
Water and Sewer Maintenance Section							
PIECOWYEW&SMT1							
STATUS	LOCATION:	REPAIR TYPE	PRIORITY	JOB #	Loc:	ACTIVITY:	GL
Current	1006 Tiffin Crescent	Sanitary Connection	MBL	664	3112	5-6500	05-270
2nd	Massey Drive & Marr Avenue	Water Main	MP1	146	3114	5-6100	02-150
Hold	175/303 Delaronde Road	Repair C/B Lead	MP1	775	3079	5-6710	07-310
Hold	Arnhem St. & McNaughton Avenue	Hydrant (McAvery)	MP2	243	3059	5-6300	02-160
Hold	Field House	Water Connection	MBL	49246	1724067	5-6410	02-170
:W&SMT2							
STATUS	LOCATION:	REPAIR TYPE	PRIORITY	JOB #	Loc:	ACTIVITY:	GL
Hold	Clarence Avenue - 8th St. - 9th St.	Water Main	MP1	146	3115	5-6100	02-150
Hold	15 Moxon Crescent	Sanitary Connection	MBL	664	3108	5-6500	05-270
			MBL				
			MBL				
			MBL				
:W&SMT3							
STATUS	LOCATION:	REPAIR TYPE	PRIORITY	JOB #	Loc:	ACTIVITY:	GL
Hold	Dudley Street	Cathodic Protection	FMP	46806	1724067	5-6100	17-596
			MBL				
			MBL				
			MBL				
Hold	8th Street Yard	Cleanup Yard	MBL	49195	1724067	5-6100	02-150
:W&SMT4							
STATUS	LOCATION:	REPAIR TYPE	PRIORITY	JOB #	Loc:	ACTIVITY:	GL
			MBL				
Hold	Isabella Street / Eastlake Avenue	Repair C/B Lead	MBL	48959	1724067	5-6710	07-310
Hold	Isabella Street / Eastlake Avenue	Valve (WPL)	MP2	146	3031	5-6200	02-150
			MBL				
			MBL				
DAY OFF/EDO		VACATION:		SICK:			
Ross, Young, Maskwa & Crews, Olchove,		Hilton, Swidzinski				Collins - Medical	
Priority Legend							
(MP1) Maintenance Priority - (MBL) Maintenance Backlog - (MPS) Maintenance Program Support - (FMP) F							

Daily Work Sheet Section B

- Section B shows additional information.

on					
SIGNING:	GIS	UTL>LOC:	STAFFING:		COMMENTS:
S/S			LABOURERS -	Parker/Klassen	
On Site			BACKHOE OPERATOR -	Dmytrowich - 2343	
On Site	27126		T/A OPERATORS -	Pingue	Gravel required to complete
On Site	23535				
Crew					
SIGNING:	GIS	UTL>LOC:	STAFFING:		COMMENTS:
S/S			LABOURERS -		No homes out!
S/S			BACKHOE OPERATOR -		
			T/A OPERATORS -		
SIGNING:	GIS	UTL>LOC:	STAFFING:		COMMENTS:
N/A			LABOURERS -		
			BACKHOE OPERATOR -		
			T/A OPERATORS -		
N/A					
SIGNING:	GIS	UTL>LOC:	STAFFING:		COMMENTS:
			LABOURERS -		
S/S			BACKHOE OPERATOR -		
S/S	1168		T/A OPERATORS -		
OTHER:			ADDITIONAL STAFFING:		COMMENTS:
			Loader - Cousins @ Landfill -		
unded Maintenance Program					

Daily Work Sheet Section C

- Section C shows work pending.

Pending Water & Sewer Work									
STATUS	LOCATION:	REPAIR TYPE:	PRIORITY	JOB #	Loc:	ACTIVITY:	GL	SIGNING:	GIS
Hold	Boychuck Dr. South of Taylor St.	Storm MH F&C	MBL	760	3010	5-6620	07-310	Crew	21925
Hold	Boychuck Dr. South of Taylor St.	Storm MH F&C	MBL	760	3010	5-6620	07-310	Crew	21924
Hold	4200 Block Taylor Street	Sanitary MH F&C	MBL	563		5-6620	05-260	Crew	8575
Hold	412 Avenue C South	Curb Stop (C&S)	MP2	48237	1724067	5-6400	02-170	S/S	3813
Hold	213 Avenue I South	Curb Stop (C&S)	MP2	48150	1724067	5-6400	02-170	S/S	
Hold	4th Avenue & 23th Street	San Bev Top	MBL	573	3012	5-6620	05-260	S/S	
Hold	Ottawa Avenue / 20th Street	San Bev Top	FMP	573	3068	5-6620	05-260	S/S	

Pick up Materials

- The Supervisor IV will pick up the required materials



Choosing Equipment

- Choose the excavator/backhoe and shoring types based on size of excavation and soil condition.



Trailer Placement









- Locate trailers clear of the excavation.



Marking Utilities

- Representatives from utility companies can field locate their lines if required.

APWA Colour Codes

	Electric Power Lines
	Gas, Oil, or Steam
	Communications Lines, Cables, or Conduit
	Potable Water
	Reclaimed Water, Irrigation, and Slurry Lines
	Sewers and Drain Lines
	Temporary Survey Markings
	Proposed Excavation


Cutting Asphalt or Concrete

- Cut the asphalt or concrete before excavating.



Recycling Asphalt or Concrete

- The asphalt or concrete can be recycled.



Emergency Water Supply Trailer

- Water trailers and temporary hook ups are options to consider when there is a water outage.



Excavation

- Excavate on the opposite side of the sewermain.



Spoil Pile

- The trench will be sorted into salvageable material and non-salvageable material.




Utility Depths

- Establish utility depths using the feeling rod.



Supported Utility

- Other Utilities must be supported



Gas Line Safety

- In the event of a natural gas line hit the machine shall be immediately turned off



Power Line Safety

- Should a power line come to rest on the equipment, do not exit the equipment




Excavation Safety

- Don't get between the excavator bucket and the truck being loaded.



Trench Cave-in

- Protective structures must be used.



Submersible Pump

- Should an excess amount of water be observed in the trench, install a submersible pump.



Shoring on Trailer

- Inspect the shoring before use.



Unloading Shoring

- Hook up shoring lifting chains appropriately



Hydraulic Expansion of Shoring

- Expand shoring side panels to be tight against the excavation walls.



Shoring Installation

- Use excavator/backhoe to install shoring.



Tool Disinfection

- All tools must be disinfected prior to use on a water main.



Tool Disinfection

- Soak items with disinfectant solution (Min 5% Sodium Hypo-chlorite solution).




Enter Excavation

- Bottom Labourer may enter excavation.



Three Points of Contact

- Keep three point of contact with the ladder.



Expose Pipe

- Remove soil with tunnelling shovel.



Break Identification

- Pipe is washed and inspected.



Split Pipe

- A split pipe is longitudinal cracks in the pipe.



Hole Break in Pipe

- Hole pipe breaks occur due to pipe corrosion.



Shear Pipe Break

- Shear breaks occur due to soil movement.



Repair Clamp Installation



Pipe Cleaning

- Clean each side of the break with rasp or scraper.



Pipe Washing

- Wash the pipe toughly before installing the repair clamp.




Repair Clamps

- Back off all nuts to the end of each stud.



Preparing Repair Clamp

- Pull the two-piece clamp apart.



Placement of Repair Clamp

- Place lug section of the clamp onto the pipe
- Ensure that the tapered gasket ends are not folded over.
- Slide the bolt section of the clamp under the pipe.



Connecting Repair Clamp

- Grab the lifter bar on each side of the bolt section.
- Gently spread and pull upwards until they snap into place.



Run Down The Nuts

- Uniformly run down the nuts on each side of the clamp.



Tighten the Nuts

- Alternately tighten all nuts in uniform steps.



Torque Bolts

- Torque up to 75 - 80 ft-lbs.
- The clamp is now installed.



Torque Wrench

- Shows torque in ft-lbs.



Treated Block

- Install treated blocks under pipe.



Sacrificial Anode

- The 36-lb. sacrificial anode must be installed on metallic pipe.



Preparation for Anode Installation

- File pipe to bare metal at the point of anode wire attachment.




Cadweld Charge

- Prep Cadweld with charge.



Anode Wire Sleeve

- Insert stripped anode wire into sleeve



Attach Wire to Pipe

- Attach the anode's wire to pipe, with the Cadweld connector.



Lighting Cadweld

- Prepare to light Cadweld.
- A face shield and goggles must be worn when igniting the Cadweld.



Ignite Charge

- Cadweld lit.



Check Weld

- Check that weld is attached.



Protect Weld

- Protect the weld from corrosion.



Wet Anode

- Soak anodes with water before backfilling.



Pipe Replacement



Quickie Saw

- Use a quickie saw to cut the pipe.
- A face shield and goggles must be worn.



Cutting Pipe

- When cutting pipe, start at the bottom of pipe and work your way to the top.



Cutting A/C Pipe

- Tile cutters shall be used for A/C pipe.
- Keep pipe wet while cutting to minimize airborne particles.



Hydraulic Pipe Cutters

- Hydraulic cutters can be used on CI pipe.



Removing Cut Pipe

- After cutting both ends of failure, a crowbar may be used to dislodge flawed pipe from existing bedding,
- Check both ends of cut pipe for corrosion or cracks.



Lifting Pipe From Excavation

- Safely remove pipe from excavation.



Measuring Pipe

- Take overall measurement of the space between existing pipes.



Cutting Pipe

- Cut the new pipe.



Couplers and Clamps

- Approved couplers may be used.
- Repair clamps are not to be used as couplers!



Transition Coupler

- Reducing or transition couplers.




Maxi-fit Coupler on Pipe

- The Maxi-fit coupler can be slipped over pipe, without dismantling



Bolt Torque Pattern

- Couplers bolts are tightened and torqued in the pattern shown.



Protecto Caps

- Zinc anode Protecto caps are supplied with this type of coupler.



Support Coupler

- Support coupler by snugly placing treated block beneath it.



Bedding Material

- Use correct materials to support and cover the replacement pipe and coupler.



Robar Coupler

- Robar couplers will require dismantling.



Collar and Gasket

- The collar and gasket is slipped over existing pipe.



Centre Coupler

- Centre sleeve and remaining end gaskets over new pipe.



Torque Coupler Bolts

- The Robar couplers are torqued in the same pattern as the Maxi-fits.



Blocking Robar Coupler

- The Robar coupler is blocked for support.



Anodes for Robar Couplers

- The Robar couplers will require mechanically attached anodes.





Post Repair

Exit Excavation

- Remove all hand tools from excavation.
- Exit and remove ladder.



Throttle valve

- Disinfect the throttle valve and hydrant port.



Flushing Pipe

- Slowly bleed the air from the water-main



Water Testing

- Perform water quality tests.



Inspect Pipe For Leaks

- Pressurize the water main and observe the repair for leaks.



Shoring Removal

- Excavator/backhoe operator removes shoring from excavation, placing it on a trailer.





Backfilling

Excavation Backfilling

- Remove unsuitable material



Backfilling Connections

- Cover services connection and mains with 150mm [6in.] of granular material and compact.



Non-shrink Backfill

- Non-shrink backfill shall be used where concrete or brick will be replaced.



Backfilling Other Utilities

- Ensure utilities are supported according to the specifications of the owner of the utility.




Acceptable Backfill Material

- Acceptable quality of backfill material



Methods of Compaction

- Mechanical Methods of compaction are required.



Handheld Plate Tamper

- Backfill is 150mm [6inch.] lifts.



Hydraulic Tamper

- Hydraulic tamper [excavator attachment] cannot be used closer than 1m [3ft.] directly above pipe or service.



Vibratory Roller

- Vibratory roller is best suitable for larger excavations and should be used in 150mm [6 inch.] lifts.



Bucket Tamping

- Bucket tamping should be avoided.



Finished Backfill

- Leave adequate room for asphalt or concrete as per the Roadway Section's instruction.



Road Signs


- Remove unnecessary road signs.



Site Restoration

- Others will perform the site restoration.



A person wearing a blue long-sleeved shirt and orange shorts is operating a large blue and black hydraulic jackhammer. The jackhammer is positioned vertically, with its bit pointing downwards into a concrete surface. The person's hands are visible, gripping the handle of the tool. The background shows a rough, grey concrete wall and a wooden plank lying on the ground. The text "Thank You" and "Are there any Questions?" is overlaid on the image in a black serif font.

Thank You
Are there any Questions?