


LADDER BEAM CONSTRUCTION

Equivalent Acceptance to 2-ply Beam of Equally Sized Members

- 1. Additional blocking required every 16" o.c. minimum.
- 2. Vertical blocking is required to be attached to the sides of posts to provide continuous support from bottom of beam to top of foundation.
- 3. Joists may only bear on the beam. Joists may not be hung off the ladder beam.



Updated 01/23/2018 Page **1** of **1**